

**HAMILTON STANDARD**



SVHSER 7077

NASA CR-

151030

LIGHTWEIGHT LONG LIFE HEAT EXCHANGER  
FINAL REPORT

BY

EARL K. MOORE

PREPARED UNDER CONTRACT NAS 9-14494

BY

HAMILTON STANDARD

DIVISION OF UNITED TECHNOLOGIES CORPORATION

WINDSOR LOCKS, CONNECTICUT

FOR

NATIONAL AERONAUTICS AND SPACE ADMINISTRATION

LYNDON B. JOHNSON SPACE CENTER

HOUSTON, TEXAS 77058

JULY, 1976

(NASA-CR-151030) LIGHTWEIGHT LONG LIFE HEAT  
EXCHANGER Final Report (Hamilton Standard,  
Windsor Locks, Conn.) 160 p HC A08/MF A01  
CSCL 20D

N77-10468

Unclas

08958

G3/34 - 08958  
INPUT BRANCH

LIGHTWEIGHT LONG LIFE HEAT EXCHANGER  
FINAL REPORT

BY

EARL K. MOORE

PREPARED UNDER CONTRACT NAS 9-14494

BY

HAMILTON STANDARD  
DIVISION OF UNITED TECHNOLOGIES CORPORATION  
WINDSOR LOCKS, CONNECTICUT

FOR

NATIONAL AERONAUTICS AND SPACE ADMINISTRATION  
LYNDON B. JOHNSON SPACE CENTER  
HOUSTON, TEXAS 77058

JULY, 1976

ABSTRACT  
LIGHTWEIGHT LONG LIFE HEAT EXCHANGER  
FINAL REPORT  
BY  
EARL K. MOORE  
CONTRACT NAS 9-14494  
JULY, 1976

This report describes the design, fabrication, and test of a heat exchanger intended to be a direct replacement for the Shuttle ECS condensing heat exchanger. The objective was to achieve a weight reduction of at least forty percent.

FOREWORD

This report has been prepared by the Hamilton Standard Division of the United Technologies Corporation for the National Aeronautics and Space Administration, Lyndon B. Johnson Space Center in accordance with the requirements of Contract NAS 9-14494; Lightweight Long Life Heat Exchanger. This report covers all of the work accomplished during the period of the contract, January 13, 1975 to October, 1976. The basic objective of the program was to design, manufacture, and test a Shuttle orbiter flight configuration lightweight long life heat exchanger weighing no more than 60 percent of an equivalent stainless steel heat exchanger. Personnel responsible for the conduct of this program were Mr. F. H. Greenwood and Mr. H. Brose, Program Managers, and Mr. E. K. Moore, Program Engineer. Appreciation is expressed to Mr. B. S. Blum of the Hamilton Standard Materials Department and Mr. G. Coleman, Manufacturing Engineer, and to Mr. Frank Collier, Technical Monitor for NASA/JSC.



TABLE OF CONTENTS

<u>Title</u>	<u>Page No.</u>
SUMMARY	1
INTRODUCTION	2
CONCLUSIONS	3
RECOMMENDATIONS	4
DISCUSSION	5
FABRICATION OF LAMINATES	5
DESIGN OF FLIGHT CONFIGURATION HEAT EXCHANGER	6
Analytical Study	6
Design Layout	14
Detail Drawings	16
Quality Assurance	16
Reliability	16
Safety	16
FABRICATION OF HEAT EXCHANGER	16
Feasibility Core Fabrication	23
Heat Exchanger Fabrication	35
TEST OF HEAT EXCHANGER	41
Test Plan	41
Test	41
Weight	42
Visual Examination	42
Coating Wettability	42
Proof and Leakage	51
Performance	54
Post Performance Proof and Leakage	59
Coating Wettability	63
Weight	63
Post Test Visual Examination	63
APPENDIX A - PRESSURE DROP CALCULATIONS	A-i
APPENDIX B - TEST PLAN	B-i
APPENDIX C - TEST LOGS	C-i
APPENDIX D - ABBREVIATIONS AND SYMBOLS	D-i

LIST OF FIGURES

<u>Figure No.</u>	<u>Title</u>	<u>Page No.</u>
1	Fin Height Effect on Core Weight	13
2	Shuttle ARS Vibration Input	15
3	Core Drawing, SVSK 90347	17
4	Heat Exchanger Drawing, SVSK 90348	19
5	Core Section	24
6	Feasibility Test Core	25
7	Slurper Module	26
8	Feasibility Test Core With Slurper Modules	27
9	Air Outlet End with Slurpers and Air Inlet End	28
10	Slurper Outlet End	29
11	Feasibility Core No. 1	30
12	AMS 4006 and 4025 Closure Bars	31
13	Air Closure Bars	32
14	Second Feasibility Core	33
15	Second Feasibility Core	34
16	Second Feasibility Core	36
17	Module Showing Collapsed Areas	37
18	Module Showing Partial Melting of Fins	38
19	Module Showing Migration of Silicon	39
20	Heat Exchanger Secondary Side	43
21	Bottom View	44
22	Primary Side	45
23	Top View	46

LIST OF FIGURES  
(Continued)

<u>Figure No.</u>	<u>Title</u>	<u>Page No.</u>
24	Air Inlet	47
25	Air Outlet	48
26	3/4 View - Primary Side	49
27	3/4 View - Secondary Side	50
28	Core Volume Determination Setup	52
29	Heat Exchanger Effectiveness Versus Airflow (Dry)	57
30	Heat Exchanger Effectiveness Versus Percent Latent Load	58
31	Airside Pressure Drop (Dry)	60
32	Airside Pressure Drop Versus Latent Load	61
33	Heat Exchanger Air Side Leakage	62

LIST OF TABLES

<u>Table No.</u>	<u>Title</u>	<u>Page No.</u>
I	Typical Test Results	7
II	Lightweight Long Life Heat Exchanger Design Requirements	8
III	Final Design Details	9
IIIA	Input Data	10
IV	Design Requirements and Representative Test Data Points	55
V	Performance Data Lightweight Long Life Heat Exchanger II	56

SUMMARY

A Shuttle orbiter flight configuration aluminum heat exchanger was designed, fabricated, and tested. The heat exchanger utilized aluminum clad titanium composite parting sheets for protection against parting sheet pin hole corrosion. The heat exchanger, which is fully interchangeable with the Shuttle condensing heat exchanger, includes slurpers (a means for removing condensed water from the downstream face of the heat exchanger), and both the core air passes and slurpers were hydrophilic coated to enhance wettability. The test program included performance tests which demonstrated the adequacy of the design and confirmed the predicted weight savings.

Calculations and data pertaining to this program were originated in U.S. customary units and then converted to S.I. units.

## INTRODUCTION

In 1971, Hamilton Standard initiated an Internal Research and Development (IR&D) program to develop a lightweight long life heat exchanger. The basis of achieving lightweight combined with long life was the development of a composite aluminum-titanium sheet material capable of withstanding pitting corrosion which may occur when aluminum is exposed to wet air. The work showed that a weight savings of forty percent of a comparable stainless steel heat exchanger could be realized. The IR&D work also included extensive testing to demonstrate that aluminum is compatible with a stainless steel water loop. It also showed that interface problems, aluminum to stainless steel, should not exist.

As a result of the success of the IR&D program, the NASA initiated Contract NAS 9-13552 to evaluate the potential of a Lightweight Long Life Heat Exchanger for the Shuttle ECS. During that program, the manufacture of composite sheets was refined, and a full scale Shuttle type condensing heat exchanger was designed, fabricated, and tested, demonstrating the suitability of the composite sheet approach for long life, lightweight application. The NASA then established Contract NAS 9-14494 to design, fabricate, and test a flight representative lightweight heat exchanger to be directly interchangeable with the Shuttle stainless steel condensing heat exchanger. The aluminum heat exchanger met the requirements to be at least 40% lighter than the equivalent stainless steel unit.

CONCLUSIONS

A lightweight long life aluminum heat exchanger, fully interchangeable with the Shuttle condensing heat exchanger, has been designed and manufactured with production type tools and tested and shown to meet Shuttle performance requirements and the weight reduction expected.

RECOMMENDATIONS

It is recommended that the heat exchanger manufactured during this program be utilized for testing by the NASA to demonstrate the long term compatibility of an aluminum heat exchanger in a stainless steel water system.



## DISCUSSION

The discussion of the program is divided into the several major task areas. These are; Fabrication of Laminates, Design, Heat Exchanger Fabrication, and Test. Each major task represents a major element of the program work breakdown structure.

### FABRICATION OF LAMINATES

The procedures for fabricating the composite parting sheets were established during previous IR&D work, were refined during the previous program, and used without change, with one exception, for manufacturing the laminates for this program. The one change was the substitution of chemical cleaning for abrasive cleaning of the titanium foil.

The current heat exchanger design utilizes twenty water passes, each requiring three laminated parting sheets. During the previous program, a yield of 70 percent of the laminates had been realized. By slightly modifying tooling, two parting sheets could be cut from one laminate; and considering that details for three cores were to be fabricated and a feasibility core to be made, the number of laminates to be manufactured was:

$$\frac{20 \times 3 \times 3}{.7 \times 2} + \frac{12 \times 2}{.7 \times 2} = 146$$

Therefore, material for 150 laminates was procured and processed in two groups of 75 laminates each.

Ultrasonic inspection was used to inspect all laminates used and to select samples for destructive examination. The destructive examination, which consisted of 180° bend tests for delamination, showed that only laminates with gross ultrasonic indications would not be suitable for use; and on this basis, less than five percent of all laminates inspected were rejected.

Twelve sheets with various types of indications were used in the fabrication of the feasibility cores discussed later; and in the destructive examination of those cores, no evidence of delamination was found, confirming the adequacy of the ultrasonic inspection process and that the laminate fabrication procedures are successful.

## DESIGN OF FLIGHT CONFIGURATION HEAT EXCHANGER

Analytical Study

Although the heat exchanger designed and fabricated during the previous program was designed to Shuttle requirements, changes in those requirements occurred during that program. Therefore, after completing life testing in the previous program, the heat exchanger was subjected to several tests at the changed conditions. Table I shows a sample of the results. The unit met thermal requirements but demonstrated a pressure drop slightly higher than requirements. Further, by the time the current design had begun, requirements had again changed as shown in Table II.

A number of configurations were analyzed in order to optimize the design in terms of envelope, minimum weight, and manufacturing simplicity. The details of the final design are shown in Table III, with the nomenclature used defined in Table IIIA.

The previous configuration, utilizing aluminum fins with a high thermal conductance and, therefore, high fin efficiency had been constructed with the largest practical fin height to achieve minimum weight. With the increase in gas flow rate, fin effectiveness is reduced, and the selection of 1.548 cm (0.645 inch) fins was reviewed to determine if prior conclusions remain valid. The results are shown in Figure 1. Because of the particular balance between fin conductivity and gas conductance in the original design, a high fin was warranted. This conclusion appears to remain valid for the revised condition, although with significantly less magnitude when considering fin heights over approximately 1.2 cm (0.5 inches). The effect of the gas side parting sheet (utilized to separate and support the two fins needed when total height exceeds 1.08 cm (0.450 inches)) is included in this analysis to produce a step weight change. At the higher gas flow rate, Figure 1 shows that a change to lower fin heights is warranted even though fin effectiveness is less.

This change necessitates three additional core configuration changes. Core height is limited by Shuttle envelope, but the fraction of this height consumed by air passages must remain reasonably constant to conform to air pressure drop limitation. Therefore, as gas fin height is reduced, liquid fin height should be proportionately reduced. This reduction increases water pressure drop, but for this design was relieved by reducing the number of cold passes from six to four. The slight loss in performance was regained by increasing cold fin density from 4.7 to 7.1 fins per cm (12 to 18 fins per inch).

Pressure loss calculations indicate that specification requirements are met and are included in Appendix A of this report for reference.

TABLE I  
TYPICAL TEST RESULTS

<u>Parameter</u>	<u>Requirement</u>		<u>Result</u>	
	<u>S.I. Units</u>	<u>U.S. Units</u>	<u>S.I. Units</u>	<u>U.S. Units</u>
H <sub>2</sub> O Flow kg/sec (lb/hr)	0.09	725	0.09	725
H <sub>2</sub> O Temperature in °C (°F)	7.0	44.6	7.1	44.8
H <sub>2</sub> O Temperature out °C (°F)	15.7	60.3	15.8	60.5
Air Flow kg/sec (lb/hr)	0.176	1398	1.816	1404
Air Temperature in °C (°F)	26.8	80.3	26.9	80.4
Air Temperature out °C (°F)	10.3	50.5	9.9	49.9
Air Delta P H/m <sup>2</sup> (in. H <sub>2</sub> O)	199.26	0.8	216.7	0.87
Dew Point in °C (°F)	11.2	52.1	11.1	52
Dew Point out °C (°F)	10.3	50.5	9.4	49

TABLE II  
LIGHTWEIGHT LONG LIFE HEAT EXCHANGER DESIGN REQUIREMENTS

<u>Parameter</u>	<u>Original</u>		<u>Current</u>	
	<u>S.I. Units</u>	<u>U.S. Units</u>	<u>S.I. Units</u>	<u>U.S. Units</u>
Outlet Total Pressure kN/m <sup>2</sup> (psia)	101.4	14.7	102.0	14.8
Gas Flow kg/sec (lbs/hr)	0.111	880	0.172	1366
Gas Inlet Temperature °C (°F)	36.1	97	40.0	104
Gas Outlet Temperature °C (°F)	9.74	49.54	10.1	50.1
Inlet Dew Point °C (°F)	16.1	61	14.2	57.6
H <sub>2</sub> O Inlet Temperature °C (°F)	4.4	40	6.4	43.5
H <sub>2</sub> O Flow kg/sec (lbs/hr)	0.076	600	0.127	1009
Max. Air Side Dry Delta P N/m <sup>2</sup> (in. H <sub>2</sub> O)	96.39	0.387	149.45	0.6
Max. Air Side Wet Delta P N/m <sup>2</sup> (in. H <sub>2</sub> O)		--	199.26	0.8
Q Sensible Watts (Btu/hr)	2976	10160	5225	17842
Q Latent Watts (Btu/hr)	1074	3667	1028	3509
H <sub>2</sub> O Outlet Temperature °C (°F)	17.2	63	18.0	64.4

TABLE IIIFINAL DESIGN DETAILS

3/ 5 10:35

## INPUT DATA

6.300 LHOT	22.770 WH	1. NPH	.425-15.	-.005OR	HOT FINS
9.500 LCOLD	16.820 WC	4. NPC	.050-18.	-.005OR	COLD FINS
9.465 LNF	104.00 THIN	115.0 CM		.0100 PP	
.400 SF	43.50 TCIN	.100 DM		1.00 DPF	
.01000 AHIN	14.70 PB	.622 CL	3.65 CNU	3.65 HNU	

## OUTPUT INFO.

.8913 EF	297.456 OS	56.795 OLAT	7.57 WT
.0147 SDPH	26.810 HAH	577.99 RNH	.0968 VDRY
.5944 SDPC	296.831 HAC	165.57 RNC	.2310 VWET
50.11 THOUT	64.56 TCOUT	19. NH	20. NC
.00766 AHOUT	76.57 TX	55.56 TY	57.30 TSIN
.2400 CPH	.0150 CFH	.0435 VFH	.075 DFH
1.0000 CPC	.3400 CFC	2.7000 VFC	62.400 DFC
8.89 HNUC	7.40 CNUC		

TABLE IIIAINPUT DATA

L Hot	Hot Length, cm (in)
L Cold	Cold Length, cm (in)
LNF	No Flow Length, cm (in)
SF	Safety Factor
AHIN	Inlet Absolute Humidity - kg H <sub>2</sub> O/kg dry gas (lb H <sub>2</sub> O/lb dry gas)
WH	Hot Weight Flow - kg/sec (lb/min)
WC	Cold Weight Flow - kg/sec (lb/min)
THIN	Hot Inlet Temperature - °C (°F)
TCIN	Cold Inlet Temperature - °C (°F)
PB	Gas Inlet Pressure - kN/m <sup>2</sup>
NPH	Number of Hot Passes
X1PC	Number of Cold Passes
CM	Metal Thermal Conductivity - watts/m °C (Btu/hr ft-°F)
DM	Metal Density - kg/m <sup>3</sup> (lb/in <sup>3</sup> )
CL	$\frac{18}{\text{Gas Molecular Weight}}$
PP	Parting Plate Thickness - mm (in)
DPF	Correction Factor for Condensign Pressure Drop (= 1 for Dry Delta P)
HNU	Hot Side Nusselt Number
CNU	Cold Sid Nusselt Number
Hot Fins	Height-fin/cm-thick - cm, fm/cm, mm (in, f/in, in)
Cold Fins	Height-fin/cm-thick - cm, f/cm, mm (in, f/in, in)
EF	Effectivity - %

TABLE IIIA  
(Continued)

SDPH	Hot Side Pressure Drop - $\text{kN/m}^2$ (psi)
SDPC	Cold Side Pressure Drop - $\text{kN/m}^2$ (psi)
THOUT	Hot Side Outlet Temperature - $^{\circ}\text{C}$ ( $^{\circ}\text{F}$ )
AHOUT	Outlet Absolute Humidity - $\text{kg H}_2\text{O/kg dry gas}$ (lbs $\text{H}_2\text{O/lbs dry gas}$ )
CPH	Hot Fluid Specific Heat - $\text{Joules/kg } ^{\circ}\text{C}$ (Btu/lb $^{\circ}\text{F}$ )
CPC	Hot Fluid Thermal Conductivity - $\text{watts/m}^2 \text{ } ^{\circ}\text{C}$ (Btu/hr ft $^{\circ}\text{F}$ )
HNUC	Calculated Hot Nusselt Number
QS	Sensible Heat - watts (Btu/min)
HAH	Hot Side Conductance - $\text{watts/}^{\circ}\text{C}$ (Btu/min $^{\circ}\text{F}$ )
HAC	Cold Side Conductance - $\text{watts/}^{\circ}\text{C}$ (Btu/min $^{\circ}\text{F}$ )
TCOUT	Cold Side Outlet Temperature - $^{\circ}\text{C}$ ( $^{\circ}\text{F}$ )
TX	Hot Side Temperature at Pinch Point $^{\circ}\text{C}$ ( $^{\circ}\text{F}$ )
CPH	Hot Side Thermal Conductivity - $\text{watts/m-}^{\circ}\text{C}$ (Btu/hr ft $^{\circ}\text{F}$ )
CFC	Cold Side Thermal Conductivity - $\text{watts/m-}^{\circ}\text{C}$ (Btu/hr ft $^{\circ}\text{F}$ )
CNUC	Calculated Cold Side Nusselt Number
Q LAT	Latent Heat - watts (Btu/min)
RNH	Hot Side Reynolds Number
RNC	Cold Side Reynolds Number
NH	Number of Hot Fin Layers
TY	Cold Side Temperature at Pinch Point $^{\circ}\text{C}$ ( $^{\circ}\text{F}$ )
VFH	Hot Fluid Viscosity - $\text{N sec/m}^2$ (lb/ft hr) abs. visc.
VFC	Cold Fluid Viscosity - $\text{N sec/m}^2$ (lb/ft hr)

TABLE IIIA  
(Continued)

WT	Weight of Fins and Parting Sheets - kg (lbs)
VDRY	Dry Volume m <sup>3</sup> (ft <sup>3</sup> )
VWET	Wet Volume m <sup>3</sup> (ft <sup>3</sup> )
NC	Number of Cold Fin Layers
TSIN	Inlet Dew Point °C (°F)
DFH	Hot Fluid Density kg/m <sup>3</sup> - (lbs/ft <sup>3</sup> )
DFC	Cold Fluid Density kg/m <sup>3</sup> - (lbs/ft <sup>3</sup> )






FIGURE 1. FIN HEIGHT EFFECT ON CORE WEIGHT

### Design Layout

In addition to the thermal design discussed in the previous section, other design considerations were as follows:

Proof Pressure	
Water Side	618 kPa (75 psig)
Air Side	136 kPa (5 psig)
Leakage	No bubbles at proof pressure
Vibration	See Figure 2
Water Delta P	8.27 kPa (1.2 psi at 950 lb/hr)
Air Side Delta P	199 Pa (0.8 in H <sub>2</sub> O at rated flow)
Weight	11.65 kg max (25.694 lbs max)

These requirements were achieved as shown below:

Proof Pressure - Minimum safety factor of 1.9.

Leakage - All welded or brazed construction - tested at proof pressure.

Vibration - Lowest safety factor is 1.5.

Water Delta P - Calculated to be 182.5 Pa (0.733 in H<sub>2</sub>O) or a 64 percent margin.

Air Delta P - Calculated to be 149.7 Pa (0.601 in H<sub>2</sub>O) or a 33 percent margin.

Weight - 11.12 kg (24.91 lbs) including five percent growth factor.

One major difference between the previous unit and the current design is the inclusion of slurpers on the latter. The slurper design requires that the air side fins extend from the face of the core over the slurper surface. This requirement, coupled with the thin water passes, virtually ruled out the possibility of weld repair of water passes without damage to the air fins. Therefore, a new manufacturing sequence was established which allowed the fabrication of the heat exchanger in four basic steps:

1. Brazing and weld repair of water modules
2. Core brazing without slurpers
3. Slurper fabrication
4. Final assembly including coating of core and slurpers, attachment of slurpers, headers, and mounting feet.




FIGURE 2. SHUTTLE ARS VIBRATION INPUT

### Detail Drawings

Following completion of the layout, the final manufacturing drawings were made. Figure 3 shows the core drawing, while Figure 4 shows the heat exchanger drawing.

### Quality Assurance

The design of the unit was such that known quality problems were eliminated. For example, the possibility of trapped brazing flux was avoided by the use of fluxless brazing. The possibility of poorly laminated parting sheets was reduced by the use of 100 percent ultrasonic inspection along with destructive sampling. In addition, the design of the unit was such that cleanliness of all parts could be attained and maintained throughout the assembly and braze process. The unit is capable of being cleaned, as an assembly, by the use of appropriate flushing procedures.

### Reliability

As a completely brazed and welded unit with no moving parts, the only realistic failure mode is through corrosion of the parting sheets. The use of the laminated titanium sheets precludes this mode of failure. All other parts are tolerant of corrosion because of their thickness.

### Safety


The unit was designed with safety margins which have been demonstrated during previous flight programs to provide adequate safety margins. The unit was tested at a proof pressure of 1.5 times the maximum normal operating pressure.

## FABRICATION OF HEAT EXCHANGER

Because of the four step fabrication process planned for the heat exchanger, it was felt advisable to fabricate a feasibility core before committing the full scale parts, including the expensive composite parting sheets, to the four step sequence. Accordingly, this discussion of heat exchanger fabrication is divided into two parts; feasibility core fabrication and flight configuration fabrication.










FIGURE 4 - HEAT EXCHANGER DRAWING, SVSK 90348 - CONTINUED

FOLDOUT FRAME 1

FOLDOUT FRAME 2






FIGURE 4 - HEAT EXCHANGER DRAWING, SVSK 90348 - CONTINUED



### Feasibility Core Fabrication


A feasibility core was designed using the same materials as the flight configuration but not intended to be operational; i.e., no headers, hydrophilic coating, or mounting provisions. The design used parting sheets the approximate size of the full scale core, 15.24 cm x 25.4 cm (6 in. x 10 in.), but contained only four water modules rather than the twenty utilized by the full size heat exchanger. See Figures 5 through 8. Fin sizes and closure bar sizes were the same as the full size unit. Two of the four modules made used AMS 4025 closure bar material for evaluation purposes, while the other two used AMS 4006, the material called out for the full scale core. Leakage tests of the modules showed the AMS 4006 to be significantly better than AMS 4025.

Brazing the modules into a core initially produced poor results. The third attempt resulted in acceptable brazes. The first feasibility core, Figures 9 and 10, contained excellent water and air fin to parting sheet brazes, good AMS 4006 closure bar brazes, poor AMS 4025 brazes, and poor air closure bar to parting sheet brazes. Figure 11 shows typical air fin and water fin to parting sheet brazes, Figure 12 compares the AMS 4025, and AMS 4006 results, and Figure 13 the air closure bar brazes.

Extensive metallurgical analyses including microphotographs, scanning electron microscope, x-ray analysis, and microprobe analysis were utilized in an effort to find the cause of the poor braze found in the first two feasibility cores. The results, while not conclusive, suggested two possible modes, operating singly or together, which could have caused the inadequate braze. The results showed no contaminants which would have caused poor braze, but a higher than normal magnesium content (approximately 1% versus a normal 0.6%) was noted in fins adjacent to the closure bars. Also noted was that although excellent wetting of both fins and laminate was achieved (See Figure 14), little braze material remained at the closure bar-laminate interface. This suggests that the excellent wetting of both closure bar and laminate surfaces caused by the high magnesium concentration present also resulted in excessive flow of the braze material across adjacent surfaces instead of remaining in the joint through capillary action. This excessive flow or wetting appears to be confirmed by the surface flow of braze material on fins adjacent to the closure bar. Figure 15 shows the extent to which braze alloy flowed both from the top downward and the bottom upward as well as "modules" of braze material.

ELC  
2/25/75

REV A 5/14/75



NO REQUIRED <sup>(A)</sup> REDUNDANT LAYER MODULES, INNER

MAT'L ① FINS: .050 high x 15 per inch x .005 thick, Ruffled.  
2 REQ'D/MOD 5.8 wide x 9.8 long MAT'L: HS 3906

② CLOSURE BARS: .050 high x .100 wide

4 REQ'D/MOD - 10 in. long

2 REQ'D/MOD 3.8" Mat'l - AMS 4006

2 REQ'D/MOD - 5.8

③ PARTING SHEETS 6" x 10" x .012 (.014 optional)

3 REQ'D/MOD MAT'L - AA3003

④ BRAZE SHEETS - 6 x 10 x .002 (.0015 opt)

4 REQ'D/MOD ALCOA 718 (713)

⑤ MAKE 2 USING ALCOA 718 AND 2 USING ALCOA 713

⑥ MODULE

FIGURE 5  
CORE SECTION

SKM  
2/25/75  
REV 5/14/75

NO REQ'D 1 (ONE) ASSEMBLY

MAT'L'S - ① 4 WATER MODULES

② AIR FINS .425 high x 15 per inch x .005 thick, ruffled  
3 REQ'D 6.150" Long x 9.688 wide MAT'L HS 3906

③ Closure bars .426 x .156 P/N 565967 6.84" Long.  
6 REQ'D AMS 4006 (AA 3003 REF)

④ Baffle sheet 6 x 10  
Alcoa. 718  
6 REQ'D

⑤ END SHEETS  
AMS 4006, .046-.054  
Thick. 2 required.





FIGURE 6 FEASIBILITY TEST CORE



NO REQD - 2 SLURPER MODULES

MATERIALS (1) COVER - .010, .012, or .014 ALUMINUM  
AA3003


(A) (2) CLOSURE BAR - .080 X .101  
AA6061

(3) BRAZE FOIL - ALCOA 718  
AS REQD

(B) UNLESS OTHERWISE SPECIFIED USE ±.030 ON ALL DIMS


SLURPER MODULE

FIGURE 7




REV A WCD  
4-3-75  
E/pu  
3/12/75

FIGURE 8  
FEASIBILITY TEST CORE WITH SLURPER MODULES





AIR OUTLET END WITH SLURPERS



AIR INLET END

FIGURE 9







MODULE SIDE VIEW

FIGURE 10





TYPICAL AIR FIN BRAZE



TYPICAL WATER FIN BRAZE


FEASIBILITY CORE NO. 1

FIGURE 11

REPRODUCIBILITY OF THE  
ORIGINAL PAGE IS POOR




ALL FOUR  
BRAZES  
EXCELLENT



AMS 4006 CLOSURE BARS

POOR BRAZE




FAIR BRAZE

AMS 4025 CLOSURE BARS

FIGURE 12



NO PARTING  
SHEET WETTING




AIR CLOSURE BARS


FIGURE 13

REPRODUCIBILITY OF THE  
ORIGINAL PAGE IS POOR






20X MAGNIFICATION  
SURFACE WETTING



100X MAGNIFICATION  
FILLER MATERIAL

FIGURE 14 SECOND FEASIBILITY CORE





4X MAGNIFICATION

BRAZE ALLOY FLOW

FIGURE 15 SECOND FEASIBILITY CORE



The results also showed the presence of a probable aluminum oxide film separating both wetted surfaces (see Figure 16). It is believed that a heavy aluminum or magnesium oxide was present on the water modules as a result of their braze cycle, and this oxide was broken up during the braze but was penetrated by the braze alloy to allow wetting beneath the oxide. Since the alloy will not braze to the oxide, the intervening oxide precluded a satisfactory braze.

The modules surface had been lightly abraded in the area of the closure bars prior to brazing to remove the magnesium hydroxide suspected to have caused the lack of wetting in the first core. The amount of abrading used apparently was sufficient to remove the hydroxide and allow wetting but not sufficient to remove the oxide.

The third and successful feasibility core was brazed with two changes; the braze alloy was changed to Alcoa 713 (a higher melting alloy) and heavier abrasion at parting sheet edges using "Beartex", a material known from previous experience, not to leave contamination on the abraded surface. Metallurgical examination indicated "typical" fluxless brazes similar to the AMS 4006 braze of Figure 12.

#### Heat Exchanger Fabrication

After the fabrication of parting sheets, the manufacture of details and the successful feasibility core, the first of two sets of 20 modules was brazed. The first set produced several modules with "collapsed" faces between the pass separators. (See Figure 17.) Destructive examination of the worst of the modules revealed partial melting of the fins in local areas, see Figure 18; and the melting allowed "collapse" of the faces. The local melting was caused by migration of silicon from the braze alloy to the grain boundaries of the fin, lowering the melting point at the grain boundaries, see Figure 19. The migration occurs because the braze alloy has a nominal seven percent silicon, while the fin material has a nominal 0.6 percent.

Although local melting occurred, strength is relatively unaffected because in most cases material is not displaced and solidifies in its original position as in Figure 19. Before the module was destructively examined, it was leak tested using pressures to 50 psig with no apparent distortion or failure.







FIGURE 16 SECOND FEASIBILITY CORE






FIGURE 17







FIGURE 18






FIGURE 19

To prevent recurrence in the second lot of modules, several steps were taken. The furnace was recalibrated for temperature, new calibrated thermocouples were used, and the braze temperature was lowered to 1,130°F maximum; the first lot had used 1,140°F maximum with 1,135°F being attained with some scatter in the four thermocouples. The actual temperature attained with the second lot was 1,130°F with identical readings from all four thermocouples six minutes after furnace power was turned off. Visual examination of the modules showed no evidence of the local "collapse condition."

All of the modules showed excellent leak test results with leaks occurring only where expected; at the end of the center pass separator and at the water entrance and exist areas.

Twenty water modules, which had all passed leakage test, were stacked with air closure bars and fins, tack welded and brazed. Brazing was accomplished at 1,135°F with a one psi top load with mechanical stops to prevent collapse. The resulting core looked good with evidence of slight collapse at one air closure bar. A slight, unexplained sideways shift of the top three passes occurred but did not affect the heat exchanger assembly.

Leak testing and weld repair of the core followed the brazing operation. In all, approximately 20 external leaks in water modules were found. In addition, one internal leak from a secondary water pass to an air pass was found. All external leaks were successfully repaired prior to the addition of core bands, headers, and mounting brackets.

After welding of external leaks, the water core bands and headers were welded in place, mounting brackets fitted and welded, and slurpers and air headers were fitted following which the slurpers and partially completed heat exchanger had hydrophilic coating applied. The coating covered the outer surfaces of the slurpers and all the air passages in the core. Following coating, the slurpers were welded in place, using a "diffused" electron beam technique. The addition of slurper core bands, header, and end plates and air headers completed the heat exchanger. Following leak test, all openings were masked and final machining accomplished. All internal surfaces were alodined, the heat exchanger inspected, and then delivered to the test area for various tests. The final process inspection of the unit noted above had indicated a leak between the primary and secondary water circuits as a result of slurper header and/or air header welding. A leakage test at that time had shown the leak to be approximately 12 cc/min based on a calculated volume of 950 cc. Since the specific location of the leak could only be determined by destructive examination by removal of headers and the risk of losing the heat exchanger through this procedure was assessed as too great, it was decided to proceed with completion of fabrication and testing.

## TEST OF HEAT EXCHANGER

### Test Plan

A test plan was prepared and approved which was intended to demonstrate both the performance and environmental capabilities of the heat exchanger. The tests included were:

1. Weight
2. Visual Examination
3. Coating Wettability
4. Proof and Leakage
5. Performance
6. Proof and Leakage
7. Vibration
8. Proof and Leakage
9. Performance
10. Coating Wettability
11. Weight
12. Post Test Visual Examination

Late in the program when it was apparent that the difficulties in manufacturing the heat exchanger, i.e., the recycling of the feasibility module and the dual cycle to obtain satisfactory modules, had reduced resources intended for testing, the test program was shorted to exclude the environmental and associated tests on the basis that the intended use for this heat exchanger did not include a need for demonstrated structural capabilities.

The tests performed were:

1. Weight
2. Visual Examination
3. Coating Wettability
4. Proof and Leakage
5. Performance
6. Proof and Leakage
7. Coating Wettability
8. Weight
9. Post Test Visual Examination

The test plan, in its entirety, is included as Appendix A.

### Tests

Each of the tests performed is discussed below, and log sheets for the tests may be found in Appendix B.

### Weight

The heat exchanger was subjected to two vacuum drying cycles and weighed after each cycle with weights of 8.736 and 8.731 kg (19.26 and 19.25 lbs) recorded. The requirement was 9.434 kg (20.8 lbs) which is 60% of the weight of the equivalent stainless steel heat exchanger of 15.724 kg (34.67 lbs). The 8.7335 kg (19.255 lb) weight of the heat exchanger represents 55.5% of the equivalent stainless steel heat exchanger.

Note: Because a temperature controlled vacuum oven was available at the time the unit was weighed, the drying cycle used was two hours minimum at 14 mmHg maximum and 37.7°C (100°F) minimum instead of the conditions called out in the test plan.

### Visual Examination

Inspection showed a machining error (undercut) at one of the mounting bosses, but since no structural testing will be performed on this unit, no corrective action was taken. See Figure 20.

Figures 20 through 27 depict all sides of the heat exchanger after test. Before test views are not shown because there are no discernible differences. Figure 23 shows a dent, from unknown causes, that has no effect on performance or leakage that was present when testing began.

### Coating Wettability

Per the plan of test, the slurper coating was sampled in twelve places. The "contact angle" and "time to wet" requirements were met in six places and were not met in the remaining six places, although immediately after the coating had been applied a spot test in one location checked out satisfactorily. The most likely cause for the change in characteristics is contamination from some source, probably not identifiable. A possible cause could have been a burned thermocouple lead during curing of the hydrophilic coating. A low temperature lead had inadvertently been used to monitor oven temperature. At the 500°F part of the cure cycle, this lead burned giving off fumes which may have affected the thinner parts of the coating.

Since the effect of a partially contaminated slurper coating was not known, it was decided to continue testing.







FIGURE 20 SECONDARY SIDE





SS12620-4

FIGURE 21 BOTTOM VIEW







FIGURE 22 PRIMARY SIDE





SS12618-4

FIGURE 23 TOP VIEW






FIGURE 24 AIR INLET







FIGURE 25 AIR OUTLET










FIGURE 27 3/4 VIEW - SECONDARY SIDE

## Proof and Leakage

Both the primary and secondary water loops were subjected individually to 722 kPa (90 psig) pressure and checked for visible distortion; none was apparent.

In order to calculate a leak rate accurately, the volume of the test article must be known. An accurate method of determining volume is by discharging a known volume at a specific pressure into the unknown volume and noting the new pressure. The unknown volume can then be calculated. Figure 28 shows the setup for volume determination. The procedure followed was:

- a. Open valve C, close valve B, open valve A, and pressurize to 793 kPa (115 psia) and record pressure.
- b. Close valves A and C, open valve B, and allow pressure to stabilize. Record pressure.
- c. Repeat (a) and (b) twice for a total of three times.

To determine the volume of the primary coolant side, a known volume of 1,028 cc (62.73 in<sup>3</sup>) was used at a pressure of 790.8 kPa (114.7 psia). Pressure after discharge was 467.5 kPa (67.8 psia).

From  $P_1 V_1 + P_2 V_2 = P_3 (V_1 + V_2)$

where:  $P_1$  is pressure in known volume, kPa  
 $V_1$  is known volume, cc  
 $P_2$  is ambient pressure, kPa  
 $V_2$  is unknown volume, cc  
 $P_3$  is stabilized pressure, kPa

The volume of the heat exchanger coolant circuit is calculated:

$$V_2 = \frac{V_1(P_3 - P_1)}{P_2 - P_3} = 1,028 \frac{(467.5 - 790.8)}{101.4 - 467.5} = 907.97 \text{ cc}$$

The volume of the secondary side was presumed to be the same. The volume of the air side was calculated to be 25,077 cc (1,530 in<sup>3</sup>). Pressure decay tests of the primary and secondary coolant loops showed similar results; a delta P of 4.826 kPa (0.7 psi) and 2.758 kPa (0.4 psi) respectively.

Using the relationship:

PV = WRT, the leak rate can be determined:




FIGURE 28 CORE VOLUME DETERMINATION SETUP



$$W_1 = \frac{P_1 V}{RT} = \text{Conditions at start of test}$$

$$W_2 = \frac{P_2 V}{RT} = \text{Conditions at end of test}$$

Then the gas lost through leakage is:

$$W_1 - W_2 = P_1 \frac{V}{RT} - P_2 \frac{V}{RT}$$

$$\Delta W = (P_1 - P_2) \frac{V}{RT}$$

$$\Delta W = \frac{\Delta P V}{RT} \quad (\text{where } T \text{ is maintained constant for the test})$$

where  $W$  = mass of gas at pressure  $P$  and temperature  $T$   
 $V$  = volume of test article  
 $R$  = universal gas constant

If we divide  $\Delta W$  by density ( $\rho$ ) and time ( $t$ ) and let  $\frac{\Delta W}{\rho t} = lr$  then the leak rate =  $lr = \frac{\Delta P}{RT\rho t} \text{ cc/t}$

$$\text{in S.I. units } lr = 2.619 \frac{\Delta P}{Tt} \text{ for coolant side}$$

$$= 72.318 \frac{\Delta P}{Tt} \text{ for air side}$$

$$\text{in U.S. units } lr = 32,701.35 \frac{\Delta P}{Tt} \text{ for coolant side}$$

$$= 902,960.6 \frac{\Delta P}{Tt} \text{ for air side}$$

The leak rates calculated for the primary and secondary sides were 1.43 cc/min and 0.82 cc/min. These leak rates are approximately ten times less than previously noted, although a submer-sion test showed the leak to be internal (between water passes) and presumably the same leak discovered earlier.

The leak rate calculated for the air side was 51.28 cc/min. This test was not observed by the Program Engineer but based upon later observations is believed to represent fixture leakage rather than heat exchanger leakage.

### Performance

Performance testing of the lightweight long life heat exchanger was performed to demonstrate that the heat exchanger is interchangeable with Shuttle CEI Item 10 P/N 705504.

Table IV presents the heat exchanger design requirements together with a representative primary and redundant loop data point.

This demonstrates the units overall compliance with the design requirements. Table V summarizes the recorded heat exchanger performance data for each of the points tested. These data are discussed below.

To maintain a systematic approach, the data from each test was reduced according to analytical procedures outlined in the Master Test Plan. In addition, the performance of the heat exchanger was evaluated on the basis of its effectiveness value,  $\epsilon$ , which is defined as:

$$\epsilon = \frac{T_{\text{Air In}} - T_{\text{Air Out}}}{T_{\text{Air In}} - T_{\text{Water In}}}$$

The heat exchanger effectiveness is a non-dimensional grouping which possesses readily visualized physical significance since it compares actual attained heat transfer to maximum theoretical values.

A preliminary review of all performance test data indicated that the heat balances were within 10 percent. Although slight variances between inlet and outlet dew pointer readings were observed during noncondensing runs, this critical instrumentation generally could be relied upon to give accurate readings in the condensing mode.

Figure 29 presents noncondensing heat exchanger effectiveness as a function of total air flow.

This shows that for the dry operating mode the unit achieves a relatively high effectiveness level over the full range of air flow rate.

Figure 30 presents a plot of heat exchanger effectiveness versus percent latent heat load. Data is presented for the three nominal flow conditions:

PARAMETER	S. I. UNITS				ENGLISH UNITS			
	UNITS	DESIGN REQUIREMENT	REPRESENTATIVE PRIMARY LOOP POINT 13566 3B	REPRESENTATIVE REDUNDANT LOOP POINT 14141 3A	UNITS	DESIGN REQUIREMENT	REPRESENTATIVE PRIMARY LOOP POINT 13666 3B	REPRESENTATIVE REDUNDANT LOOP POINT 14141 3A
SENSIBLE HEAT TRANSFER RATE	WATTS	5232	5534	5303	BTU/HR	17842	18893	18106
LATENT HEAT TRANSFER RATE	WATTS	1029	1511	1485	BTU/HR	3509	5157	5070
AIR TEMP., IN (DRYBULB)	K	313	313	313	°F	104	104.2	103.6
AIR TEMP., IN (DEWPOINT)	K	287	287	287	°F	57.6	58.0	57.9
AIR TEMP., OUT (DRYBULB)	K	283	282	283	°F	50.1	47.8	49.4
AIR TEMP., OUT (DEWPOINT)	K	283	281	281	°F	50.1	46.8	47.0
AIR FLOW RATE	kg/HR	620	621.6	620	LB/HR	1366	1369	1365.6
AIR PRESSURE DROP (DRY)	PA	149, 4 @ 636 kg/HR	149, 5 @ 641 kg/HR *	149, 5 @ 641 kg/HR **	IN. H <sub>2</sub> O	6 @ 1400 LB/HR	6 @ 1411 LB/HR	6 @ 1411 LB/HR
AIR PRESSURE DROP (WET)	PA	199, 3 @ 636 kg/HR	169, 4 @ 641 kg/HR **	162 @ 620 kg/HR	IN. H <sub>2</sub> O	8 @ 1400 LB/HR	68 @ 1411 LB/HR	65 @ 1366 LB/HR
WATER TEMP-IN	K	279	278	279	°F	43.5	42.0	43.4
WATER TEMP-OUT	K	291	291	292	°F	64.4	64.9	66.3
WATER FLOW RATE	kg/HR	458	457.5	458.7	LB/HR	1009	1007.6	1010.3
WATER PRESSURE DROP	PA	944 @ 431 kg/HR	914 @ 457 kg/HR	909 @ 459 kg/HR	PSI	1, 2 @ 950 LB/HR	1, 3 @ 1007, 6 LB/HR	1, 3 @ 1010 LB/HR

† DRY POINT 14140.2  
 \*\* WET POINT 14142.2

TABLE IV DESIGN REQUIREMENTS AND REPRESENTATIVE TEST DATA POINTS

TABLE V PERFORMANCE DATA LIGHT-WEIGHT LONG LIFE HEAT EXCHANGER II

LOG NUMBER	TEST POINT	$\dot{m}_{AIR}$		$T_{AIR-IN}$		$T_{D.P.-IN}$		$T_{AIR-OUT}$		$T_{D.P.-OUT}$		$\dot{m}_{H_2O}$		$T_{H_2O-IN}$		$T_{H_2O-OUT}$		$Q$ SENSIBLE		$Q$ LATENT		$Q$ TOTAL (AIR)		$Q$ H <sub>2</sub> O		HEAT IMBALANCE		AIR
-	P=PRIM S=SECON	kg/HR	LB/HR	K	°F	K	°F	K	°F	K	°F	kg/HR	LB/HR	K	°F	K	°F	WATTS	BTU/HR	WATTS	BTU/HR	WATTS	BTU/HR	WATTS	BTU/HR	%	%	
13662	1	P	207.7	457.5	299	79.8	286	55.5	280	45.0	279	43.0	208.6	459.4	278	42.1	285	53.8	1139	3888	525	1792	1664	5680	1655	5651	.56	92.0
13662	1A	P	209.5	461.4	299	79.8	286	55.5	278	42.1	279	43.0	208.7	459.8	279	42.4	285	53.9	1145	3910	530	1809	1675	5718	1667	5690	.50	92.3
13662	1B	P	209.5	461.4	299	79.4	285	55.9	280	44.9	279	43.0	208.7	459.8	278	41.9	285	53.4	1139	3888	552	1885	1691	5773	1639	5594	3.10	91.9
14143	1	P	209.2	460.8	299	79.9	285	53.6	280	44.8	279	42.8	208.6	459.4	278	42.1	285	53.2	1156	3948	448	1530	1605	5479	1511	5159	5.86	92.5
14140	1	F	209.2	460.8	299	79.6	259	7.0	279	43.6	256	1.0	209.5	461.4	278	41.9	283	50.5	1162	3967	0	0	1162	3967	1149	3922	1.14	96.3
13664	2	P	641.2	1412.4	302	85.2	287	58.0	284	52.7	284	51.9	465.6	1025.6	282	49.0	290	62.7	3279	11196	907	3096	4187	14294	4186	14291	.03	89.3
13664	2A	P	641.2	1412.4	303	85.4	287	58.0	284	52.9	284	51.8	463.0	1024.3	282	49.1	290	62.8	3276	11184	918	3134	4194	14319	4160	14202	-.02	88.9
13664	2B	P	641.2	1412.4	303	85.6	287	58.0	284	52.9	284	51.8	463.8	1026.0	282	49.1	290	62.8	3296	11254	913	3116	4209	14370	4156	14189	1.26	88.9
14142	2	F	640.7	1411.2	302	85.3	286	55.5	284	52.1	283	50.5	465.6	1025.5	282	49.0	289	61.9	3349	11433	712	2430	4061	13863	3866	13198	4.79	91.3
14140	2	P	641.0	1411.8	303	85.5	269	24.5	283	50.9	268	22.5	465.4	1025.0	282	49.1	289	60.8	3419	11673	0	0	3419	11673	3513	11992	-2.73	94.5
13666	3	F	620.3	1366.2	313	104.2	279	42.3	282	47.9	281	46.9	456.6	1005.8	279	42.3	291	65.1	5485	18725	1497	5110	6982	23836	6835	23335	2.10	90.3
13666	3A	F	621.3	1368.6	313	104.4	288	58.5	282	47.9	281	47.0	457.5	1007.7	279	42.3	291	65.0	5527	18870	1564	5340	7092	24212	6863	23446	3.20	90.4
13666	3B	F	621.6	1369.2	313	104.2	287	58.0	282	47.8	281	46.8	457.5	1007.6	278	42.0	291	64.9	5534	18893	1511	5157	7045	24050	6856	23406	2.60	90.5
14140	3	F	619.4	1364.4	313	104.5	270	26.0	281	46.1	269	23.0	457.9	1008.6	278	43.2	290	62.9	5606	19139	0	0	5606	19139	5790	19768	-3.30	95.1
14142	3	F	620.0	1365.6	313	103.8	287	57.7	282	49.2	282	48.0	458.4	1009.6	279	43.6	292	65.6	5338	18224	1341	4578	6679	22802	6530	22292	2.24	90.5
14141	3	S	620.0	1365.6	313	104.2	267	21.0	265	46.6	265	18.0	458.4	1009.6	279	43.6	291	63.8	5500	18778	0	0	5500	18778	5574	20394	-8.60	94.6
14141	3A	S	620.0	1365.6	313	103.6	297	57.9	283	49.4	281	47.0	458.7	1010.3	279	43.4	292	66.3	5503	18106	1485	5070	6789	23176	6771	23116	-.26	89.8
13666	4	S	619.4	1364.4	313	104.1	287	58.0	281	48.3	281	46.0	457.6	1007.9	278	42.0	291	65.5	5450	19607	1585	5411	7046	24056	6958	23753	1.26	89.5
13666	4A	S	620.0	1365.6	313	104.3	288	59.5	282	48.5	281	46.5	458.0	1008.9	278	42.0	292	65.6	5467	18664	1620	5531	7087	24196	6954	23741	1.88	89.5
13666	4B	S	620.3	1366.2	313	104.7	288	59.5	283	49.7	282	47.8	457.9	1008.7	279	43.5	292	66.6	5500	18402	1628	5558	7019	23962	6825	23300	2.76	89.6
13666	4C	S	620.0	1365.6	313	104.6	288	59.5	282	49.4	281	47.5	457.9	1008.7	279	43.5	292	66.5	5388	18430	1669	5697	7067	24126	6804	23229	3.70	89.9

REPRODUCIBILITY OF 1L  
ORIGINAL PAGE IS POOR

FOLDOUT FRAME 1

FOLDOUT FRAME 2




FIGURE 29 HEAT EXCHANGER EFFECTIVENESS VS. AIRFLOW (DRY)




FIGURE 30 HEAT EXCHANGER EFFECTIVENESS VERSUS PERCENT LATENT LOAD

2. Air Flow = 620 kg/hr (1,366 lb/hr), Water Flow = 458 kg/hr (1,009 lb/hr)
3. Air Flow = 640 kg/hr (1,412 lb/hr), Water Flow = 465 kg/hr (1,025 lb/hr)

The two latter conditions are sufficiently close together that one line was used to represent the data trend. These data demonstrated compliance with the design requirement, as represented by an effectiveness value.

The decrease in effectiveness as latent load is increased is normal and results primarily from air flow maldistribution caused by water droplets collecting on the airway fin surface. This effect is minimized through the use of hydrophilic coatings and operation with the functional water collection device.

Figure 31 is a plot of heat exchanger air side dry pressure drop versus flow rate. The design point is again included for reference and shows that the unit operates within its design limitations. As the heat exchanger switched to the condensing mode, the air side pressure drop increased over the dry value, as shown in Figure 32.

The heat exchanger water pressure drop was found to be 8.27 kPa (33.2 inches H<sub>2</sub>O) at 431.3 kg/hr (950 lb/hr) which meets the design requirement for the unit.

#### Post Performance Proof and Leakage

The leakage tests were performed per the test plan and showed no leakage in 30 minutes for either water circuit and 5.7 cc/min leakage on the air side. Because of the differences noted in coolant side leakage, this test was rerun.

It was found that coolant side leakage had decreased to an extent where a 30 minute test was too short to determine the rate. The primary side was tested to achieve a 6.894 kPa (1.0 psi) decrease in pressure. Two hundred twelve minutes were required resulting in a rate of 0.29 cc/min. To confirm this result, the unit was submerged, and the escaping gas was trapped. In one hour 8.0 cc's were collected or 0.13 cc/min, confirming the pressure decay test result. This rate, again, is appreciably below the rate previously measured and probably represents gradual closure of the leak by aluminum corrosion products. On September 14, 1976 this leakage was again measured and had further decreased to 0.03 cc/min.

After correcting air side fixture leakage, the rate was found to be 5.69 cc/min, and the leak was located at a weld in the slurper header, see Figure 33. This leak was epoxy sealed after all other tests were completed.




FIGURE 31 AIRSIDE PRESSURE DROP (DRY)







FIGURE 32 AIRSIDE PRESSURE DROP VS. LATENT LOAD



SS12567-4

FIGURE 33 AIR SIDE LEAKAGE

### Coating Wettability .

The time-to-wet and contact angle test results were virtually unchanged from pretest conditions.

### Weight

Two post test dry and weigh cycles showed the weight of the heat exchanger to be unchanged at 8.736 kg (19.26 lbs).

### Post Test Visual Examination

As previously noted, no discernible differences were noted, and Figures 18 through 25 are post test photographs.

APPENDIX A  
PRESSURE DROP CALCULATIONS

# HX AIR SIDE PRESSURE DROP CALCULATIONS

## INLET HEADER

$$1411 \frac{\#}{\text{HR}} = 3919 \frac{\#}{\text{SEC}} = 5.429 \frac{\text{FT}^3}{\text{SEC}} \quad P = 0.0722 \frac{\#}{\text{FT}^3}$$

$$\text{INLET HEADER AREA} = \frac{\pi (8)^2}{4 \cdot 144} = 0.3491 \text{ FT}^2$$

$$\text{Flow Velocity} = \frac{Q}{A} = \frac{5.429}{0.3491} = 15.6 \frac{\text{FT}}{\text{SEC}}$$

$$HL = \frac{PV^2}{2gc} = \frac{0.0722 (15.6)^2}{64.4 \cdot 144} = .00188 \text{ Psi}$$

$$\text{ENTRANCE \& EXIT EFFECTS : } \Delta P = \frac{PV^2}{2gc} \left[ (K_c + 1 - \alpha^2) - (1 - \alpha^2 - K_e) \frac{v_2}{v_1} \right]$$

$$\Delta P = \frac{0.0722 (10.9)^2}{64.4 \cdot 144} \left[ (1.08 + 1 - .481) - (1 - .481 + .5) \cdot 927 \right]$$

$$\Delta P = 0.0006 \text{ Psi}$$

## OUTLET HEADER

$$1411 \frac{\#}{\text{HR}} = .3919 \frac{\#}{\text{SEC}} = 5.034 \frac{\text{FT}^3}{\text{SEC}} \quad f = 0.07786$$

$$A = \frac{\pi (6)^2}{4 \cdot 144} = 0.1963 \text{ FT}^2 \quad \text{HEADER AREA}$$

$$\text{Flow Velocity} = \frac{Q}{A} = \frac{5.034}{.1963} = 25.64 \frac{\text{FT}}{\text{SEC}}$$

$$HL = \frac{fV^2}{2gc} = \frac{.07786 (25.64)^2}{64.4 \cdot 144} = 0.0055 \text{ PSI}$$

$$0.5 \text{ VELOCITY HEAD LOSS FOR OUTLET HEADER} = .00276 \text{ PSI}$$

## TOTAL AIR SIDE PRESSURE LOSS

CORE LOSS	.01649 PSI
INLET HEADER	.00188 PSI
ENTRANCE & EXIT EFFECTS	.00060 PSI
OUTLET HEADER	.00276 PSI
	<u>.02173 PSI</u>
	= .601" H <sub>2</sub> O

# COOLANT PRESSURE LOSS

$$\frac{725 \#}{HR} = \frac{0.201 \#}{SEC} = \frac{0.00323 \cdot FT^3}{SEC} \quad P = 62.4 \frac{\#}{FT^3}$$

$$INLET \text{ LINE AREA} = \frac{\pi (.4)^2}{4 \cdot 144} = 0.000872 \text{ FT}^2$$

$$Flow \text{ Velocity} = \frac{Q}{A} = \frac{.00323}{.000872} = 3.70 \frac{FT}{SEC}$$

$$HL = \frac{PV^2}{2g_c} = \frac{62.4 (3.7)^2}{64.4 \cdot 144} = 0.09212 \text{ PSI}$$

$$1.5 \times HL = 0.1382 \text{ PSI}$$

$$\begin{array}{lcl} INLET \ \& \ OUTLET \ HEADERS & = \ 0.1382 \text{ PSI} \\ CORE \ LOSS & = \ 0.5944 \text{ PSI} \\ TOTAL & = \ 0.7326 \text{ PSI} \end{array}$$

APPENDIX B  
TEST PLAN



PLAN NUMBER		
C43-002		
REVISION/DATE	PAGE	OF
A 9/2/75		

LIGHTWEIGHT LONG LIFE HEAT EXCHANGER  
FLIGHT CONFIGURATION

MASTER TEST PLAN

PREPARED UNDER CONTRACT NAS 9-14494

BY

HAMILTON STANDARD  
DIVISION OF UNITED TECHNOLOGIES

WINDSOR LOCKS, CONNECTICUT  
FOR  
NATIONAL AERONAUTICS AND SPACE ADMINISTRATION

LYNDON B. JOHNSON SPACE CENTER

HOUSTON TEXAS

JUNE 1975

Prepared by *E.K. Moore*  
E.K. Moore, Program Engineer

Approved by *F.H. Greenwood*  
F.H. Greenwood, Program Manager

## TABLE OF CONTENTS

	<u>Page</u>
1.0 SCOPE	1
2.0 APPLICABLE DOCUMENTS	1
2.1 Government	1
2.2 Hamilton Standard	1
3.0 GENERAL	1
3.1 Item Description	1
3.2 Test Purpose	2
3.3 Tests	2
3.4 Test Facilities	2
4.0 TEST REQUIREMENTS	2
4.1 Weight	2
4.2 Visual Examination	3
4.3 Coating Characteristics	4
4.4 Proof Pressure and Leakage Test	5
4.5 Performance	6
4.6 Vibration	8
Figure 1 Shuttle ARS Vibration Input	13
Figure 2 Weight Log Sheet	14
Figure 3 Coating Characteristics Log Sheet	15
Figure 4 Primary Coolant Loop Proof and Leakage Setup	16
Figure 5 Secondary Loop Proof and Leakage Set-up	17
Figure 6 Air Loop Proof and Leakage Set-up	18
Figure 7 Proof and Leakage Log Sheet	19
Figure 8 Performance Set-up	20
Figure 9 Slurper Test Set-up	21
Figure 10 Air Side Pressure Drop Log Sheet	22
Figure 11 Primary Loop Pressure Drop Log Sheet	23
Figure 12 Secondary Loop Pressure Drop Log Sheet	24
Figure 13 Performance Log Sheet	25
Figure 14 Heat Balance Calculation Form	26
Figure 15 Vibration Set-up	28
Figure 16 Vibration-Operation	29
Figure 17 Vibration Log Sheet	30
Figure 18 Slurper $\Delta P$ Without Air Flow Log Sheet	31
Figure 19 Slurper $\Delta P$ With Air Flow Log Sheet	32
Table I Instrumentation	33
Table II Air Circuit Pressure Drop Conditions	34
Table III Coolant Circuit Pressure Drop Conditions	35
Table IV Dry Performance Conditions	36
Table V Wet Performance Conditions	37
Table VI Slurper $\Delta P$ Without Air Flow Conditions	38

PLAN NUMBER	
C43-002	
REVISION/DATE	PAGE OF
A 9/2/75	

## 1.0 SCOPE

This test plan defines the testing of a Lightweight Long Life Heat Exchanger (LLLHX-II) being conducted for the National Aeronautics and Space Administration Lyndon B. Johnson Space Center, NASA Contract 9-14494.

## 2.0 APPLICABLE DOCUMENTS

### 2.1 Government

MIL-P-27401 Propellant pressuring Agent, Nitrogen

### 2.2 Hamilton Standard

HS 3150 Cleanliness Levels, High - Processing, Testing and Preservation of parts subject to

SVHS TBD Coating Hydrophilic. Aluminum Heat Exchangers.

SVSK 90348 Drawing, Heat Exchanger Condenser.

SV 755504 Drawing, Humidity Control Heat Exchanger, Item 10.

## 3.0 GENERAL

3.1 Item Description - The Lightweight Long Life Heat Exchanger (LLLHX-II), Hamilton Standard P/N SVSK 90348-1, is designed to be completely interchangeable with the Shuttle condensing heat exchangers CEI 10. As tested and delivered, the LLLHX does not include insulation and flight instrumentation. The component was designed to the following conditions:

Outlet Total Pressure, psia	14.8
Gas Flow, lbs/Hr	1366
Gas Inlet Temperature, °F	104
Gas Outlet Temperature, °F	50.1
Inlet Dew Point °F	57.6
Water Inlet Temperature °F	43.5
Water Flow, lbs/Hr	1009
Water Outlet Temperature (ref) °F	64.4
Max. Gas Side Wet ΔP, in. H <sub>2</sub> O	0.8
Max. Gas Side Dry ΔP, in. H <sub>2</sub> O	0.6
Q Sensible, BTU/Hr	17,842
Q Latent, BTU/Hr	3,509
Weight, lbs max.	20.8
Water ΔP, in. H <sub>2</sub> O	38.8
Vibration	Fig 1

The heat exchanger is a fluxless brazed, aluminum unit incorporating aluminum clad titanium parting sheets. It contains nineteen parallel, single pass gas passages for condensing moisture and cooling gas. It also contains twenty, four pass primary water cooling passages and twenty, four pass secondary (redundant), water cooling passages. Mounting and connection points are identical to Shuttle CEI item 10. The weight, including insulation and flight instruments is calculated to be 23.72 lbs. nominal or 56.4% of the comparable Shuttle stainless steel unit.

- 3.2 Test Purpose - The purpose of the test program is to demonstrate that the item is interchangeable with Shuttle P/N SV75504 item 10, and is capable of withstanding the vibratory loads of Figure 1.
- 3.3 Tests - After completion of the fabrication of the item, which includes proof and leakage tests, the item shall be subjected to the following tests in the sequence specified:

Test	Title	Test per paragraph
1.	Weight	4.1
2.	Visual Examination	4.2
3.	Coating Wettability	4.3
4.	Proof and Leakage	4.4
5.	Performance	4.5
6.	Proof and Leakage	4.4
7.	Vibration	4.6
8.	Proof and Leakage	4.4
9.	Performance	4.5
10.	Coating Wettability	4.3
11.	Weight	4.1
12.	Post Test Visual Examination	4.2

- 3.4 Test Facilities - Unless otherwise indicated, all testing shall be conducted in the Space System Department test laboratories at Hamilton Standard. Alternate facilities may be used, if necessary, if approved in writing by the cognizant Program Engineer.

#### 4.0 TEST REQUIREMENTS

Test objectives, descriptions, procedures, and pass-fail criteria are contained in the following paragraphs. Deviations may only be made if authorized in writing by the cognizant Program Engineer.

##### 4.1 Weight

- 4.1.1 Objective - The objective of the weight measurement is to establish that the design requirement of a weight no greater than 60% of the comparable Shuttle HX has not been exceeded or to detect any weight change resulting from testing.

4.1.2 Description

4.1.2.1 Test Setup - The item shall be weighed on a scale having a full scale accuracy of at least 1% and a range no greater than 100 lbs. and capable of being read to + 0.1 lbs. Prior to weighing, a vacuum chamber shall be used to dry the item thoroughly.

4.1.2.2 Procedure - The item without port closures and free of all extraneous material, shall be dried for 24 hours minimum at a pressure of 1500 microns maximum and a temperature of 60°F minimum. Within one hour after the drying period and without wetting the item, weigh and record the item weight on Log of Test. HSF 175.1A per Figure 2. Repeat the drying and weighing sequence. The two recorded weights shall agree within 0.1 lb. If the weights do not agree, the drying - weighing sequence shall be repeated until agreement is reached with two consecutive readings.

4.1.3 Pass - Fail Criteria - A weight greater than 20.8 lbs. shall require approval from the NASA to proceed with testing.

4.2 Visual Examination

4.2.1 Objective - The objective of the visual examination is to define a baseline of the visual appearance of the heat exchanger, describing apparent defects or damage for comparison before and after test.

4.2.2 Description

4.2.2.1 Test Setup - The heat exchanger shall be placed on a well lighted, clean bench in the SSD laboratory or inspection department. It shall be free of chips, dirt and liquids and the ports shall be open. Photographs may be taken in the Photo Laboratory.

4.2.2.2 Procedure - The item shall be visually examined on exterior surfaces for evidence of dirt manufacturing residue, stains, dents, burns or other marks or blemishes. Inlet and outlet water ports shall be subjected to particular attention. Visual observations shall be recorded on a Log of Test. HSF 157.1A. Photographs shall be used to record the general appearance of the item and shall include sufficient views to show all six sides of the item. In particular, the surfaces of the inlet and outlet water ports shall be photographed as well as those portions of the hydrophilic coating that are readily photographed. In addition, the inlet and outlet of the air fins shall be photographed.

#### 4.2.3 Pass - Fail Criteria

- a. The item shall be free of all dirt, chips, residues and other foreign material.
- b. Damage which could affect the performance or function of the unit shall be cause for rejection. The cognizant Program Engineer shall judge the suitability of the item for continued testing.

#### 4.3 Coating Characteristics

4.3.1 Objective - The objective of the coating characteristics test is to establish a baseline against which deterioration of the hydrophilic coating can be measured and to demonstrate that the coating is acceptable.


#### 4.3.2 Description

4.3.2.1 Test Setup - The characteristics test shall be performed on the dry heat exchanger on a clean dry well lighted bench. A 10X microscope with an angular micrometer disk reticule is required along with a 5 microliter water droplet syringe and a vial of clean water.

#### 4.3.2.2 Procedure

4.3.2.2.1 Contact Angle - Using the 10X microscope, measure the contact angle of a 5 microliter water droplet placed on the coated slurper surface. Droplets shall be placed in at least twelve places. Record the location and contact angle of each droplet per Figure 3.

4.3.2.2.2 Time to Wet - At a minimum of twelve places, place a 5 microliter water droplet midway between slurper holes and measure the time to the nearest 0.1 seconds to wet to the slurper holes. Record the data per Figure 3.  
Note: The contact angle is defined as the angle subtended between the coating surface and a line tangent to the water droplet at the point of contact with the surface such that the water droplet is included within the angle.



#### 4.3.3 Pass - Fail Criteria

- a. If the average contact angle is greater than 10 degrees, the cognizant SSD Materials Engineer shall disposition the suitability of the coating. If the angle is equal to or less than 10 degrees, the item is suitable for continued testing.



- b. If the average time to wet is greater than 5 seconds, the cognizant SSD Materials Engineer shall disposition the suitability of the coating. If the time to wet is equal to or less than 5 seconds, the item is suitable for continued testing.

4.4 Proof Pressure and Leakage Test

- 4.4.1 Objective - The objective of the Proof Pressure and Leakage test is to verify the pressure and leakage integrity of the heat exchanger.

4.4.2 Test Setup

- (a) The proof and leakage test shall be conducted on a bench within the SSD laboratory.

- (b) The following instrumentation is required:

<u>Instrument</u>	<u>Min. Range</u>	<u>Units</u>	<u>Type</u>	<u>Accuracy</u>
Thermometer	32-100	°F	Hg	+1/2°F
Thermocouples	32-100	°F	Copper/Const.	+1°F System
Pressure Gage	0-100	psig	Bourdon	+1%F.S.
Pressure Gage	0-5	psig	Bourdon	+1%F.S.

- (c) Test equipment shall include the following:

<u>Item</u>	<u>P/N</u>
Fitting Closures, Water	NPN-LLLHX-II-1
Closures, Air	SV755539CT200 SV755508CT209-4
	SV755539CT201 SV755508CT209-5
	SV755508CT208-4 SV755503CT200
	SV755508CT208-5 SV755503CT201(3)

- (d) Test setups are given in Figures 4, 5, and 6.

- (e) Pressurant supply shall be Nitrogen per MIL-P-27401.

4.4.3 Procedure

- (a) The heat exchanger is comprised of an air circuit and a primary and a redundant water circuit. These circuits may be tested in the most convenient sequence.
- (b) Attach circuit closures.
- (c) To test a circuit, attach regulated pressure supply to

the circuit inlet with the outlet sealed. The other two circuits should be vented to ambient.

- (d) Pressurize, slowly, to the pressure specified below. Close the supply shutoff and record the supply pressure. Record a second reading after ten minutes. If pressure decay is apparent, continue recording at 5 minute intervals for a total of 30 minutes max.

Note: Item and ambient temperatures shall be stable within  $\pm 2^{\circ}\text{F}$  during the test.

- (e) If the pressure cannot be maintained, attempt to locate the leak. Mark any leaks located and advise the cognizant Engineer. Weld repairs are acceptable.
- (f) Repeat the procedure above for the other two circuits.

<u>Heat Exchanger Circuit</u>	<u>Pressure (min.)</u>	<u>Units</u>
Air	1.8	psid
Water (2)	90	psig

- (g) Data shall be recorded for each run per Figure 7.
- (h) Data corrections shall be required for variations in ambient and/or item temperature.
- (i) A photograph of a typical test setup shall be taken prior to removal of the heat exchanger to the next test, on the first test only.

#### 4.4.4 Pass - Fail Criteria

- (a) There shall be no detectable leakage in ten minutes, after temperature corrections.
- (b) There shall be no visible permanent deformation.

#### 4.5 Performance

- 4.5.1. Objective - The objective of the performance test is to demonstrate that the heat exchanger is interchangeable with Shuttle CEI item 10 P/N 755504.

#### 4.5.2 Test Setup

- (a) The performance test shall be conducted within the Space System Department Laboratory.

PLAN NUMBER C43-002		
REVISION/DATE	PAGE	OF

- (b) The required instrumentation is listed on Table I.
- (c) The test shall be conducted on test rig 61 using an ancillary coolant water supply.
- (d) The heat exchanger shall be set up and instrumented per Figures 8 and 9.
- (e) Data shall be visually read and manually recorded on Log of Test Form, HSF175.1A. In addition, the serial number and calibration date of all instrumentation shall be recorded.
- (f) Fluid cleanliness inherent to the test rigs shall be adequate.
- (g) Test fluids shall be laboratory quality air and steam, provided by Rig 61 and the ancillary coolant water supply.

#### 4.5.3 Procedure

- (a) Mount the heat exchanger, make fluid connections (air and water) as shown on Figures 8 and 9, and instrument per Figures 8 and 9 and Table I. Fill the heat exchanger using the vacuum fill method with the pressure at 0.1 psia max before introducing water. During instrumentation, record the identification, serial number and calibration date of each instrument used. Photograph the test setup at some convenient time prior to completion of tests.

Note: Any instrument changes during test shall be recorded on the test data sheet.

- (b) Measure the air, primary water and slurper pressure drops per Tables II, III, and VI recording the data per Figs. 10, 11, and 18. Change the coolant plumbing to the secondary cooling circuit and repeat the test points of Table III, recording the coolant pressure drops per Figure 12.
- (c) The performance conditions to be tested are listed in Tables IV and V. The sequence of runs shall be that providing maximum test efficiency, except that all dry tests shall be completed before any wet tests are performed.
- (d) The conditions for a test point shall be established per procedures inherent to rig operations. Record data every five minutes until conditions have stabilized and then continue recording at 5 minute intervals for a minimum of 5 additional readings. Conditions may be considered stabilized when inlet and outlet water and air temperature

conditions do not vary more than 1.5°F for three consecutive readings. Record data per Figure 13.

- (e) Proceed to next test point and repeat the above procedure until all test points per Tables IV and V have been tested and are accepted by Engineering. Then change the water connection to the secondary water loop and repeat wet performance test point No. 3.
- (f) After the tests of Table IV have been completed, maintain the conditions of test point 2 of the Table IV and measure slurper pressure drops per Table VI and record data per Figure 19.
- (g) Upon completion of heat balance calculations. per Figure 14, the cognizant Engineer shall indicate rejection or acceptance of the run by so noting and initialing on the data sheet. If a balance cannot be obtained, the operator shall repeat the run in the most efficient operating sequence.
- (h) At completion of testing, the air and water circuits shall be dried by purging with dry air at 160-200°F for one hour. Air and water circuits shall be capped or covered with polyethylene film.

4.5.4 Pass - Fail Criteria - The following conditions shall be met for Test Point 2 of Table V:

Air Outlet Temperature	53°F max
Air Outlet Dew Point	53°F max
Air Pressure Drop	0.8 in. H <sub>2</sub> O max
Coolant Pressure Drop	38.8 in. H <sub>2</sub> O max

#### 4.6 Vibration

4.6.1 Objective - The objective of the vibration test is to determine the ability of the laminate construction of the heat exchanger to withstand "shuttle" level vibration as defined herein.

#### 4.6.2 Test Setup

- (a) The test shall be conducted on the vibration test rig in the Hamilton Standard Space Systems Laboratory, or at an approved vendor facility.
- (b) Vibration Test Tolerances - Plus or minus one db overall rms acceleration and plus or minus three db on acceleration spectral density (g<sup>2</sup>/Hz) for the following:

Frequency Range

Maximum Effective Bandwidth

10 to 100 Hz

6 Hz

100 to 500 Hz

12 Hz

500 to 2000 Hz

24 Hz

Analysis sample time (T) shall equal or exceed  $50/BW$ , where BW is the effective bandwidth of the filter utilized. For swept filter analysis, analyzer filter scan rate (SR) shall, (1) not exceed  $BW/T$  Hz/second when averaging is obtained using linear integration with an integration time of T; or (2) shall be  $BW/4RC$  when averaging is obtained by smoothing with an equivalent resistance capacitance (RC) low pass filter using a time constant RC equals  $T/2$ .

Peak and Notch Tolerance - Peaks and notches may not deviate more than +3db from these limits between 500 and 2000Hz. The total frequency bandwidth of the peaks and notches deviating more than 1.5 db shall be less than 300 Hz. These tolerances are increased in roll off regions of the spectrum by +0.1 db for every one db down from the maximum level specified. All db are in terms of power ratio. Peak and notches below 500 Hz may exceed the +3 db tolerance by no more than 1.5 db and not exceed a bandwidth of 25 Hz.

Frequency Tolerance - The frequency shall be +2%.

Exposure Time Tolerance (Minutes) - The exposure time shall be + 10% - 0%.

- (c) Test Set-Up Sketch - In the space provided in HS Form 175.7, a sketch of the test item and fixture shall be made including the definition of the three orthogonal axes.
- (d) Log Sheet - An operator's log sheet, Form HSF 175.1A, shall be provided. The log sheet shall contain run number, starting time of run, axis, mode (sinusoidal or random), scan rate, g's peak, and paragraph number of the test specification which delineates the vibration level requirements.
- (e) Photographs - Photographs shall be taken which clearly illustrate the test item and set-up for each orthogonal axis. Polaroids are acceptable.



PLAN NUMBER C43-002		
REVISION/DATE	PAGE	OF

- (f) Accelerometer Signals - The unfiltered signals from the installed accelerometers shall be recorded on magnetic tape for all tests. Response data will be provided upon specific written request from project engineer.
- (g) Control Curve - A control curve shall be provided for each of the three orthogonal axis.
- (h) Recording - The vibration control accelerometer signal and any response accelerometer signal shall be recorded (and identified by voice annotation) on magnetic tape for all tests. The tape recorder shall record these signals whenever power is applied to the shaker system. System calibration information (g's/volts, etc.) sufficient to allow analysis of the vibration signals subsequent to the test, shall also be recorded on the magnetic tape and any other applicable documentation. The magnetic tapes shall be maintained as part of the permanent vibration test records. The vibration control accelerometer(s) shall be located in accordance with the fixture investigation to ensure that the specified vibration is being applied to the test specimen.
- (i) Fixture Investigation - The test fixture and test item shall be subjected to a low level filtered sinusoidal vibration in accordance with standard Hamilton Standard practice to verify the fixture response characteristics in each of the three major orthogonal axes as specified below at 2 oct/min. sweep rate:

<u>Frequency Range</u>	<u>Vibration Level</u>
5-10 Hz	0.2 inch O.A
10-2000 Hz	+1.0 g pk.

The number of transducers required to conduct the fixture scan shall be specified by the cognizant structures engineer. From the results of the scan, the engineer shall select the adequate control location and record the selection. The sweep rate may be reduced near those frequencies where control becomes difficult to maintain in order to allow the servo to respond.

It shall not be necessary to repeat the fixture investigation for subsequent tests after the initial control location has been selected.


- (j) Item Mounting - The test unit is to be fastened to the vibration test fixture TBD, which in turn will be secured to the vibration generator. The attachment of the test item to the vibration fixtures shall be in accordance with the requirements defined by the installation drawing (SVHS 755504). The three orthogonal axes are defined in Figure No. 15.
- (k) Transducer Location
  - A. Install control accelerometer on the fixture at the fixture/item interface in accordance with the results of the figure investigation.
  - B. Install response accelerometers on the test unit per design engineering or cognizant test engineering instruction at time of test.
- (l) Operation - The primary and secondary coolant loops of the test item shall be evacuated to 0.1 psia and back-filled with water prior to vibration. Each coolant loop shall be pressurized to 90+ psig. Once conditions have stabilized, shut water supply valves. Pressures shall be monitored during vibration testing. The evacuation and back-fill shall be accomplished using the test set-up in Figure 16. Record data before and after each axis vibration test on Log of Test per Figure 17.

Note: The capping of the ports may vary from Figure 16, although in each loop one end must be capped and the other end pressurized.

- 4.6.3 Test Procedure - For random vibration testing, a dynamically similar dummy shall be used in place of the test specimen, when possible, for pretest equalization(s). The final equalization prior to the test shall be accomplished using the test specimen and shall be conducted at the full specified random vibration level. The time expended during the final equalization shall be counted as part of the required test time for the random vibration test. The final equalization shall be verified by a narrow band analysis prior to initiation of the test, using effective bandwidths not exceeding those specified in paragraph 4.6.2 of this test plan. A narrow band spectral analysis shall be performed on the input control accelerometer signal once per hour during the test (analysis may be actually performed subsequent to test run) to demonstrate that the test specimen has been subjected to the specified random spectrum. All random spectral analysis shall be performed as x-y log-log plots of acceleration spectral density ( $g^2/Hz$ ) versus frequency (Hz). The test shall be exposed to the spectrum defined by Figure 1

for 48 minutes in each of three orthogonal axes. The unit is to be filled and pressurized during all vibration testing.

- 4.6.4 Pass - Fail Criteria - The test item shall not exhibit damage and/or permanent deformation and the test item must successfully pass the subsequent leakage and performance tests.




*Gu.*











PRIMARY COOLANT LOOP PROOF AND LEAKAGE

FIGURE 4



SECONDARY LOOP PROOF AND LEAKAGE

FIGURE 5



AIR LOOP PROOF AND LEAKAGE

FIGURE 6








FIGURE 8




FIGURE 9



[illegible]

FIGURE 11







TEST DATA VERIFICATION - HEAT BALANCE

Step	Item	From	Units	<u>CONDITIONS</u>											
				1	2	3	4	5	6	7	8	9	10	11	12
A	$\Delta T_a$	log	F°												
B	$q_{air\ sens}$	$A \times 0.24$	Btu/lb d. a.												
C	Inlet Vapor	$W/7000$	lb H <sub>2</sub> O/ lb/d. a.												
D	h Vapor In	Steam Tab.	Btu/lb H <sub>2</sub> O												
E	$Q_{v\ in}$	$C \times D$	Btu/lb d. a.												
F	Outlet Vapor	$W_L/7000$	lb H <sub>2</sub> O/ lb d. a.												
G	h Vapor out	Steam Tab	Btu/lb H <sub>2</sub> O												
H	$q_v\ out$	$F \times G$	Btu/lb d. a.												
J	$q_v\ sens$	E-H	Btu/lb d. a.												
K	$\Delta W_u$	C-F	lb H <sub>2</sub> O/ lb d. a.												
L	h l	Steam Tab	Btu/lb H <sub>2</sub> O												
M	$q_v\ lat.$	$K \times L$	Btu/lb d. a.												
N	$q_{total}$	B+J+M	Btu/lb d. a.												
O	ma	log	lb d. a. hr												

ECS-730022-1-012  
Page 23 A  
C43-002

FIGURE 14.

TEST DATA VERIFICATION - HEAT BALANCE (Continued)



Step	Item	From	Units	1	2	3	4	5	6	7	8	9	10	11	12
P	Q air	$N \times O$	Btu/hr												
Q	$m_{H_2O}$	log	lb H <sub>2</sub> O/ hr												
R	$\Delta T$	log	F°												
S	$Q_{H_2O}$	(1, 0) $\times Q \times R$	Btu/hr												
T	Balance	$\frac{P-S}{S} \times 100$ <u>(0±10%)</u>	%												

Hamilton  
Standard  
U  
R.  
Division of United States Army Ordnance  
WINDSOR LOCKS, CONNECTICUT 06096

ACS-750022-L-012  
Page 24 A  
C43-002


FIGURE 14 (Cont'd)

X AXIS - USE FIXTURE TBD  
Y AXIS - USE FIXTURE TBD  
Z AXIS - USE FIXTURE TBD



VIBRATION AXIS

FIGURE 15



VIBRATION OPERATION

FIGURE 16







<div style="display: flex; justify-content: space-between; align-items: center;"> <div style="font-size: 0.8em;">             100P-175 1A 1 / 56  <b>Hamilton Standard</b> DIVISION OF UNITED AIRCRAFT CORPORATION              WINDSOR LOCKS, CONNECTICUT 06096           </div> <div style="font-size: 2em; font-weight: bold; text-align: center;">U A</div> </div> <div style="text-align: center; margin-top: 10px;"> <b>SPACE &amp; LIFE SYSTEMS LABORATORY</b>  <b>LOG OF TEST</b> </div>										<div style="border-bottom: 1px solid black; padding-bottom: 2px;"> <b>TYPE OF TEST</b>              Slurper <math>\Delta P</math> with Air Flow           </div> <div style="border-bottom: 1px solid black; padding-bottom: 2px;"> <b>TEST ENGINEER</b> </div> <div style="border-bottom: 1px solid black; padding-bottom: 2px;"> <b>NAME OF RIG</b> </div> <div style="border-bottom: 1px solid black; padding-bottom: 2px;"> <b>PROJECT &amp; ENG ORDER NO.</b> </div>										<div style="border-bottom: 1px solid black; padding-bottom: 2px;"> <b>SHEET</b>      <b>OF</b> </div> <div style="border-bottom: 1px solid black; padding-bottom: 2px;"> <b>DATE</b> C43-002           </div>	
										<b>TEST PLAN NO.</b>											
										<b>MODEL NO.</b>											
										<b>PART NO.</b>											
										<b>SERIAL NO.</b>											
										<b>OPERATORS</b>											

Time	Test Point	Tin	Pin	Air	Flow	$\Delta P$	Pout			Slurper		Flow	$\Delta P$						
				DPin						Tin	Pin								
		$^{\circ}F$	Psia	$^{\circ}F$	lbs/Hr	"H <sub>2</sub> O	Psia			$^{\circ}F$	Psia	lbs/Hr	"H <sub>2</sub> O						

REMARKS

FIGURE 19

# INSTRUMENTATION

Item	Range	Accuracy
Inlet Water Flow, $\dot{M}_{H_2O}$	160-1600lbs/Hr Min	2% of reading
Inlet Water Temp., $T_{H_2O}$ in	0-100°F	$\pm 1^\circ F$
Inlet Water Press., $P_{H_2O}$ in	0-60 psia	$\pm 0.1$ psi
Inlet Air Flow, $\dot{M}$ air	0-1500lbs/Hr Min	2% of reading
Inlet Air Temp. $T$ air in	35-160°F	$\pm 1^\circ F$
Inlet Air Dew Point, TDP in	0-100°F	$\pm 2^\circ F$
Inlet Air Pressure, $P$ air in	0-20 psia	$\pm 0.1$ psi
Water Pressure Drop, $\Delta P_{H_2O}$	0-60 in $H_2O$	$\pm 0.1$ in $H_2O$
Air Pressure Drop, $\Delta P$ air	0-5 in $H_2O$	$\pm 0.1$ in $H_2O$
Water Temp. Rise, $\Delta T_{H_2O}$	0-100°F	$\pm 0.5^\circ F$
Air Temp. Drop, $\Delta T$ air	0-100°F	$\pm 0.5^\circ F$
Outlet Air Temp, $T$ air out	35-160°F	$\pm 1.0^\circ F$
Outlet Air Dew Point, TDP out	0-100	$\pm 2.0^\circ F$
Inlet Temp Diff., $\Delta T$ air in $H_2O$	0-100	$\pm 0.5^\circ F$
Inlet Temp Diff., $\Delta T$ air out $H_2O$ in	0-100	$\pm 0.5^\circ F$

TABLE I

*AIR PRESSURE DROP CONDITIONS*

TEST CONDITIONS	UNITS	TEST POINTS				Tolerance
		1	2	3	4	
AIR INLET TEMPERATURE	°F	80	80	104	80	±1
AIR INLET PRESSURE	psia	14.7	14.7	14.7	14.7	±1
AIR INLET DEWPOINT	°F	<30	<30	<30	<30	-
AIR FLOW	Lbs/Hr.	700	1000	1366	1600	±5

*TABLE II*

# COOLANT PRESSURE DROP CONDITIONS

TEST CONDITIONS	LIMITS	TEST POINTS				Tolerance
		1	2	3	4	
AIR INLET TEMPERATURE		—	—	—	—	
AIR INLET PRESSURE		—	—	—	—	
AIR INLET DEWPOINT		—	—	—	—	
AIR FLOW		—	—	—	—	
COOLANT INLET TEMPERATURE	°F	45	45	45	45	±1
COOLANT INLET PRESSURE	psig	25	25	25	25	±1
COOLANT FLOW	Lbs/ltr	600	800	1000	1200	±5

TABLE III

DRY PERFORMANCE CONDITIONS

TEST CONDITIONS	UNITS	TEST POINTS				Tolerance
		1	2	3	4	
AIR INLET TEMPERATURE	°F	79.8	85.3	104.0	—	±1
AIR INLET PRESSURE	psia	14.7	14.7	14.7	—	±1
AIR INLET DEWPOINT	°F	<30	<30	<30	—	±1
AIRFLOW	Lbs/Hr	461	1411	1366	—	±5
SLURPER AIR FLOW	Lbs/Hr	36	36	36	—	±1
COOLANT INLET TEMPERATURE	°F	42	49	43.5	—	±1
COOLANT INLET PRESSURE	psig	25	25	25	—	±1
COOLANT FLOW	Lbs/Hr	460	1025	1009	—	±5

TABLE IV

WET PERFORMANCE CONDITIONS

TEST CONDITIONS	LIMITS	TEST POINTS				Tolerance
		1	2	3	4	
AIR INLET TEMPERATURE	°F	79.8	85.3	104.0	—	±1
AIR INLET PRESSURE	psia	14.7	14.7	14.7	—	±1
AIR INLET DEWPOINT	°F	53.5	55.5	57.6	—	±0.1
AIR FLOW	Lbs/Hr	461	1411	1366	—	±5
SLURPER AIR FLOW	Lbs/Hr	36	36	36	—	±1
COOLANT INLET TEMPERATURE	°F	42	49	43.5		±0.1
COOLANT INLET PRESSURE	psig	25	25	25	—	±1
COOLANT FLOW	Lbs/Hr	460	1025	1009	—	±5

TABLE V



*SLURPER LF WITHOUT AIR FLOW*

TEST CONDITIONS.	UNITS	TEST POINTS				Tolerance
		1	2	3	4	
SLURPER INLET AIR TEMP	°F	50	50	50	50	
SLURPER INLET AIR PRESS.	PSIA	14.7	14.7	14.7	14.7	
SLURPER AIR FLOW	LBS/ HR	20	30	40	50	

TABLE VI

APPENDIX C  
TEST LOGS

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

U  
D AIRC  
A

SPACE &amp; LIFE SYSTEMS LABORATORY

### LOG OF TEST

### TYPE OF TEST

WEIGHT

**TEST ENGINEER**

E. MOORE

NAME OF RIG

12.

PROJECT & ENG. ORDER NO.

C43-400-001B

SHEET 1 OF

DATE 5-5-76

TEST PLAN NO. C 43 - 002

MODEL NO LONG LIFE HUM H.X.

PART NO SVSK 90348-1

SERIAL NO

## OPERATORS

	FIRST DRY CYCLE	SECOND DRY CYCLE	THIRD DRY CYCLE
START TIME	2030 HR	1230 hr.	
END TIME	2300 HR	1230 hr.	
TEMP. AT START	138 °F	103 °F	
TEMP. AT END	144 °F	135.0 °F	
VACUUM AT START	.5 mm	0.6 mm	
VACUUM AT END	.3 mm	0.5 mm	
TIME AT WEIGHING	5/6/76 11:20	14:30	
WEIGHT	19.24	19.25	

REMARKS:

22521

REPRODUCIBILITY OF THE  
ORIGINAL PAGE IS POOR

**Hamilton Standard**  
WINDSOR LOCKS, CONNECTICUT 06096

DIVISION OF UNITED AIRCRAFT CORPORATION



SPACE &amp; LIFE SYSTEMS LABORATORY

## LOG OF TEST

## TYPE OF TEST

Coating Characteristics

TEST ENGINEER

NAME OF RIG

PROJECT &amp; ENG. ORDER NO.

SHEET OF

DATE C43-002

TEST PLAN NO.

MODEL NO.

PART NO.

SERIAL NO.

OPERATORS

Test Point	Contact Angle	Time to Wet secs	
1 Center	$\sim 30^\circ$	$> 30 \text{ sec}$	(Left side $< 10^\circ$ & 1 sec) (R.S. $\sim 30^\circ$ 25 sec)
2 Center	$\sim 30^\circ$	$> 30 \text{ sec}$	(L.S. $< 10^\circ$ & 2 sec) (R.S. $\sim 30^\circ$ $> 30 \text{ sec}$ )
3 Center	$\sim 30^\circ$	$> 30 \text{ sec}$	(L.S. $< 10^\circ$ & 1 sec) (R.S. $\sim 30^\circ$ $> 30 \text{ sec}$ )
4 Center	$< 10^\circ$ ✓	1 sec ✓	(L.S. & R.S. OK)
5 Center	20-30°	15 sec	(L.S. $< 10^\circ$ 1 sec) (R.S. $\sim 30^\circ$ $> 30 \text{ sec}$ )
6 "	20-30°	$> 30 \text{ sec}$	(L.S. $< 10^\circ$ 1 sec) (R.S. $\sim 30^\circ$ $> 30 \text{ sec}$ )
7 "	$< 10^\circ$ ✓	1 sec ✓	(L.S. & R.S. OK)
8 "	20-30°	$> 30 \text{ sec}$	(L.S. $< 10^\circ$ 2 sec) (R.S. $\sim 30^\circ$ $> 30 \text{ sec}$ )
9 "	$< 10^\circ$ ✓	1 sec ✓	(L.S. $> 30^\circ$ $> 30 \text{ sec}$ ) (R.S. $\sim 100^\circ$ 5 sec)
10 "	$\sim 10^\circ$	5 sec ✓	(L.S. $\sim 10^\circ$ 2 sec) (R.S. $\sim 20^\circ$ 25 sec)
11 "	$< 10^\circ$ ✓	1 sec ✓	(L.S. $< 10^\circ$ 1 sec) (R.S. $> 30^\circ$ $> 30 \text{ sec}$ )
12 "	$< 10^\circ$	1 sec ✓	(L.S. 20-30° 6 sec) (R.S. 20-30° 23 sec)
Ave. Contact Angle =		Ave. Time to Wet =	

REMARKS

Slurper Head




Slurper #12 Test pt #12

Slurper #1 Test pt #1

FIGURE 3

15

R. Ruby 5/10/76



**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

**U  
A**

SPACE &amp; LIFE SYSTEMS LABORATORY

## LOG OF TEST

## TYPE OF TEST

PROOF + LKG

## TEST ENGINEER

E. K. MOORE

## NAME OF RIG

64

## PROJECT &amp; ENG. ORDER NO

C43-400-001B

SHEET 1 OF

DATE 5-10-76

TEST PLAN NO. C43-003-A

MODEL NO LLL HX-II

PART NO. SVSK 90348-1

SERIAL NO.

OPERATORS SLAHTOSKY

5-11-76  
AIR LOOP

BAROMETRIC PRESS. IN. HG.

29.89

29.86

29.76

AMB TEMP, °F

68.8

69.0

69.0

INITIAL PRESS PSIA

90.0

90.0

1.8

ITEM TEMP, °F

70.0

70.0

68.0

PRESS IN 10 MIN. PSIA

89.8

90.0

1.42

" " 15 MIN "

89.6

89.9

1.28

" " 20 MIN "

89.5

89.8

1.13

" " 25 MIN "

89.4

89.7

1.05

" " 30 MIN "

89.3

89.6

.90

TEMP IN 10 MIN. °F

70.0

70.0

68.0

" " 15 "

70.0

70.0

68.0

" " 20 "

70.0

70.0

68.0

" " 25 "

70.0

70.0

68.0

" " 30 "

70.0

70.0

68.0

REMARKS

12205

**Hamilton Standard**  
WINDSOR LOCKS, CONNECTICUT 06096

DIVISION OF UNITED AIRCRAFT CORPORATION

U  
A

SPACE &amp; LIFE SYSTEMS LABORATORY

## LOG OF TEST

## TYPE OF TEST

MEASURE LKG.

## TEST ENGINEER

E.K. MOORE

## NAME OF RIG

64

## PROJECT &amp; ENG. ORDER NO.

C43-400-001B

SHEET 1 OF

DATE 5-10-76

TEST PLAN NO C43-002A

MODEL NO LLL HX II

PART NO. SVSK 90348-1

SERIAL NO.

OPERATORS SLAHTOSKY

#	PIN	TEMP																		
RUN	PSIG	OF																		
①	100.	70.0	PRESS TO 100.0 PSIG. VALVE "A" CLOSED, "B" OPEN																	
	53.0	70.0	CLOSE VALVE "C", OPE VALVE "A". PRESS. DROPPED TO 48.0 PSIG																	
			+ UP TO 53.0																	
②	100.	70.0	SAME AS ABOVE																	
	53.2	70.0																		
③	100.	70.0	SAME AS ABOVE																	
	53.1	70.0																		

REMARKS:

22522

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

U  
A

SPACE &amp; LIFE SYSTEMS LABORATORY

## LOG OF TEST

## TYPE OF TEST

AIR SIDE PRESS DROP

## TEST ENGINEER

E.K. MOORE

## NAME OF RIG

61

## PROJECT &amp; ENG ORDER NO.

C43-400-001B

SHEET 1 OF 2

DATE 5-14-76

TEST PLAN NO. C43-002

MODEL NO. LLLHX-II

PART NO. SVSA90348-1

SERIAL NO.

OPERATORS Kuller

TIME	TEST POINT	T <sub>IN</sub> °F	T <sub>OUT</sub> °F	P <sub>IN</sub> "H <sub>2</sub> O	ΔP "H <sub>2</sub> O	D.P. IN	D.P. OUT	AIR Flow lb/Hr											
2210	1	79.9	79.9	.35	.22	27.5	27.5	699.6											
2215	1	79.8	79.9	.35	.22	26.5	26.5	699.6											
2220	1	79.8	79.9	.35	.22	26.0	26.0	699.6											
2225	1	79.8	79.9	.35	.22	26.0	26.0	699.6											
2230	1	79.8	79.9	.35	.22	26.0	26.0	699.6											
2235	1	79.7	79.8	.35	.22	26.0	26.0	699.6											
2300	2	80.6	80.8	.67	.40	20.0	20.0	999.6											
2305	2	80.7	80.8	.67	.40	19.5	19.5	999.6											
2310	2	80.7	80.8	.67	.40	18.5	18.5	999.6											
2315	2	80.6	80.7	.67	.39	17.5	17.5	999.6											
2320	2	80.6	80.7	.67	.39	17.0	17.0	999.6											
2325	2	80.6	80.7	.67	.40	16.0	16.0	999.6											
2330	2	80.6	80.7	.67	.40	16.0	16.0	999.6											

REMARKS

FIG #10

22762

WITNESSED  
5-14-76



HSF-175.1A 1/85

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

U  
A

SPACE &amp; LIFE SYSTEMS LABORATORY

## LOG OF TEST

## TYPE OF TEST

Air Side Press Drop

TEST ENGINEER

E. K. Moore

NAME OF RIG

61

PROJECT &amp; ENG. ORDER NO.

C 43-400-001B

SHEET 2 OF 2

DATE 5-17-76

TEST PLAN NO C43-002

MODEL NO. LLLHX-II

PART NO. SYSK 90348-1

SERIAL NO.

OPERATORS KULLE

Time	TEST Point	T <sub>IN</sub>	T <sub>OUT</sub>	P <sub>IN</sub>	ΔP	D.P. IN	D.P. OUT	Air Flow											
	No.	#1 OF	#2 OF	"H <sub>2</sub> O	"H <sub>2</sub> O	%	%	Lb/Hr											
1945	3	103.9	103.5	1.22	.68	29.5	21.0	1365.6											
1950	3	104.0	103.6	1.22	.68	29.0	21.0	1365.6											
1955	3	104.1	103.6	1.22	.68	29.5	21.5	1365.6											
2000	3	104.1	103.6	1.22	.68	29.5	21.5	1365.6											
2005	3	104.1	103.6	1.22	.68	29.5	21.5	1365.6											
2010	3	104.1	103.6	1.22	.68	29.5	21.5	1365.6											
2125	4	80.5	80.8	1.54	.82	11.0	8.5	1600.2											
2130	4	80.4	80.8	1.54	.82	11.0	8.5	1600.2											
2135	4	80.4	80.8	1.54	.82	11.0	8.5	1600.2											
2140	4	80.4	80.7	1.54	.82	11.0	8.5	1600.2											
2145	4	80.4	80.7	1.54	.82	11.0	8.5	1600.2											
2150	4	80.3	80.7	1.54	.82	11.0	8.5	1600.2											

REMARKS:

22595

REPRODUCIBILITY OF THE  
ORIGINAL PAGE IS POOR

UNRECORDED & INDEXED 5-17-76

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

**SPACE & LIFE SYSTEMS LABORATORY**

### LOG OF TEST

TYPE OF TEST SECONDARY  
COOLANT PRESSURE DROP

TEST ENGINEER  
E. K. Moore

NAME OF RIG

61 and 61A

PROJECT &amp; ENG. ORDER NO

C43-400-001B

SHEET 1 OF 2 DATE 5-19-76

TEST PLAN NO. C-43-002

MODEL NO. 44 HX-II

PART NO SVSK 90348-1

SERIAL NO.

OPERATORS *KJ/1E*

### Secondary H<sub>2</sub>O Loop

Time	Test Point No	Tin of	Pin F319	Flow lb/hr	ΔP "H <sub>2</sub> O	Flow K CPS	K factor
1830	1	45.1	25.0	599.3	26.0	581	1.0315
1835	1	45.0	25.0	599.3	26.0	581	1.0315
1840	1	44.9	25.0	599.3	26.0	581	1.0315
1845	1	44.9	25.0	599.3	26.0	581	1.0315
1850	1	44.9	25.0	599.3	26.0	581	1.0315
1855	1	45.0	25.0	599.3	26.0	581	1.0315
2035	2	44.6	24.7	800.4	43.0	775	1.0328
2040	2	44.6	24.7	800.4	43.0	775	1.0328
2045	2	44.5	24.7	800.4	43.0	775	1.0328
2050	2	44.5	24.7	800.4	43.0	775	1.0328
2055	2	44.6	24.7	800.4	43.0	775	1.0328
2100	2	44.6	24.7	800.4	43.0	775	1.0328
2200	3	44.5	25.1	1000.3	62.5	967	1.0345
2205	3	44.6	25.1	1000.3	62.5	967	1.0345
2210	3	44.6	25.1	1000.3	62.5	967	1.0345
2215	3	44.6	25.1	1000.3	62.5	967	1.0345
2220	3	44.6	25.1	1000.3	62.5	967	1.0345
2225	3	44.6	25.1	1000.3	62.5	967	1.0345

REMARKS:

22543

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

**SPACE & LIFE SYSTEMS LABORATORY**

### LOG OF TEST

TYPE OF TEST SECONDARY  
COOLANT PRESSURE DROP

TEST ENGINEER  
E.K. MORGAN

NAME OF RIG  
61 and 61A

PROJECT & ENG. ORDER NO.  
C43-700-001R

SHEET 2 OF 2 DATE 5-19-76

TEST PLAN NO. C43-002

MODEL NO. LLHX-II

PART NO 5VSK 90348-1

SERIAL NO.

OPERATORS *K 5/18*

## Secondary Ho Loop

TIME	TEST POINT NO	IN OF	PIN B19	Flow L <sup>3</sup> /HR	ΔP "H <sub>2</sub> O	Flow CPS	K Factor
2330	4	45.1	25.8	1201.41	85.5	1160	1.0357
2335	4	45.1	25.8	1201.41	85.5	1160	1.0357
2340	4	45.1	25.8	1201.41	85.5	1160	1.0357
2345	4	45.1	25.8	1201.41	85.5	1160	1.0357
2350	4	45.1	25.8	1201.41	85.5	1160	1.0357
2355	4	45.1	25.8	1201.41	85.5	1160	1.0357

REMARKS:

22547

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

U  
D AIRC  
A

SPACE &amp; LIFE SYSTEMS LABORATORY

### LOG OF TEST

TYPE OF TEST SECONDARY  
COOLANT Pressure Drop

**TEST ENGINEER**

E. K. Moore

NAME OF RIG

61 and 61A

PROJECT &amp; ENG. ORDER NO

C 73-400-001 B

SHEET / OF / DATE 5-29-76

TEST PLAN NO. C 43 -002

MODEL NO. LLLN-X-II

PART NO. SVSK 90348-1

**SERIAL NO.**

OPERATORS KullE

### Secondary H<sub>2</sub>O Loop

[illegible]

REMARKS:

22497

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

**U  
A**

SPACE &amp; LIFE SYSTEMS LABORATORY

## LOG OF TEST

TYPE OF TEST *Primary  
Coolant Pressure Drop*

TEST ENGINEER  
*E. K. Moore*

NAME OF RIG  
*61 end 61A*

PROJECT & ENG. ORDER NO.  
*C43-400-0018*

SHEET *1* OF *2* DATE *5-18-76*

TEST PLAN NO *C43-002*

MODEL NO. *LLHX-II*

PART NO *SYSK 90348-1*

SERIAL NO.

OPERATORS *KULLE*

*Primary H<sub>2</sub>O Loop*

Time	Test Point No.	T <sub>in</sub> of	P <sub>in</sub> Psig	Flow lb/hr	ΔP H <sub>2</sub> O	Flow CPS	K Factor
1840	1	45.2	24.9	599.3	25.5	581	1.0315
1845	1	45.3	24.9	599.3	25.5	581	1.0315
1850	1	45.2	24.9	599.3	25.5	581	1.0315
1855	1	45.2	24.9	599.3	25.5	581	1.0315
1900	1	45.3	24.9	599.3	25.5	581	1.0315
1905	1	45.2	24.9	599.3	25.5	581	1.0315
2020	2	45.6	25	800.4	42.5	775	1.0328
2025	2	45.6	25	800.4	42.5	775	1.0328
2030	2	45.7	25	800.4	42.5	775	1.0328
2035	2	45.7	25	800.4	42.5	775	1.0328
2040	2	45.6	25	800.4	42.5	775	1.0328
2045	2	46.6	25	800.4	42.5	775	1.0328
2130	3	44.6	24.9	1000.3	63.0	967	1.0345
2135	3	44.6	24.9	1000.3	63.0	967	1.0345
2140	3	44.7	24.9	1000.3	63.0	967	1.0345
2145	3	44.7	24.9	1000.3	63.0	967	1.0345
2150	3	44.6	24.9	1000.3	63.0	967	1.0345
2155	3	44.5	24.9	1000.3	63.0	967	1.0345

REMARKS

FIGURE 11

22596

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

**SPACE & LIFE SYSTEMS LABORATORY**

### LOG OF TEST

TYPE OF TEST Primary  
Coolant Pressure Drop

**TEST ENGINEER**

E. K. Moore

NAME OF RIG

61 and 61 A

PROJECT &amp; ENG ORDER NO.

C43 - 400 - 001B

SHEET 2 OF 2 DATE 5-18-76

TEST PLAN NO C 43-002

MODEL NO. 224X-II

PART NO. SVSK 90348-1

SERIAL NO

OPERATORS *Kyle*

Primary H<sub>2</sub>O Loop

Time	TEST Point No.	TIN °F	PIN PSIG	Flow lb/hr	$\Delta P$ "H <sub>2</sub> O	Flow CPS	K Factor
2300	4	44.5	30.5	1201.4	86.0	1160	1.0357
2305	4	44.5	30.5	1201.4	86.0	1160	1.0357
2310	4	44.6	30.5	1201.4	86.0	1160	1.0357
2315	4	44.6	30.5	1201.4	86.0	1160	1.0357
2320	4	44.6	30.5	1201.4	86.0	1160	1.0357
2325	4	44.6	30.5	1201.4	86.0	1160	1.0357

Delay To Switching H<sub>2</sub>O Line

REMARKS:

Point PERON Delay To Switching H<sub>2</sub>O LINE  
SEE LOG SHEET 22405

Figure 11

22599

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

**SPACE & LIFE SYSTEMS LABORATORY**

### LOG OF TEST

TYPE OF TEST Primary  
Coolant Pressure Drop

TEST ENGINEER  
E. K. Moore

NAME OF RIG  
61 and 61A

PROJECT & ENG. ORDER NO.  
C43-400-001B

SHEET 2 OF 2 DATE 5-19-76

TEST PLAN NO. C 43-002

MODEL NO. 444HX-II

PART NO. SVSK 90348-1

**SERIAL NO.**

OPERATORS *KU/2*

Primary H<sub>2</sub>O Loop

Time	Test Point No.	Tin °F	Pin PSig	Flow lb/hr	ΔP. "H <sub>2</sub> O	Flow CPS	K Factor
1605.	4	44.5	26.0	1201.4	86.0	1160	1.0357
1610	4	44.5	26.0	1201.4	86.0	1160	1.0357
1615	4	44.4	26.0	1201.4	86.0	1160	1.0357
1620	4	44.4	26.0	1201.4	86.0	1160	1.0357
1625	4	44.4	26.0	1201.4	86.0	1160	1.0357
1630	4	44.4	26.0	1201.4	86.0	1160	1.0357

REMARKS:

22495



**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

U  
D AIRC  
A

**SPACE & LIFE SYSTEMS LABORATORY**

### LOG OF TEST

TYPE OF TEST Primary  
Coolant Pressure Drop

**TEST ENGINEER**

E. K. Moore

NAME OF RIG

61 and 61A

PROJECT &amp; ENG ORDER NO

C43-400-601B

SHEET 1 OF 1 DATE 5-20-76

TEST PLAN NO C43-002

MODEL NO LLLHX-II

PART NO. SVSK 90348-1

SERIAL NO.

OPERATORS KULLE

### Primary H<sub>2</sub>O Loop

Time	TEST Point No.	TIN °F	PIN PSIG	Flow L <sup>3</sup> /hr	ΔP H <sub>2</sub> O	Flow CPS	K Factor
2110	4	44.7	60	1201.4	86.0	1160	1.0357
2115	4	44.7	60	1201.4	86.0	1160	1.0357
2120	4	44.7	60	1201.4	86.0	1160	1.0357
2125	4	44.7	60	1201.4	86.0	1160	1.0357
2130	4	44.7	60	1201.4	86.0	1160	1.0357
2135	4	44.7	60	1201.4	86.0	1160	1.0357

REMARKS.

22498

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

SPACE &amp; LIFE SYSTEMS LABORATORY

### LOG OF TEST

### TYPE OF TEST

SLURPER  $\Delta P$  w/o Air Flow

**TEST ENGINEER**

E. K. Mooré

NAME OF RIG

61 2nd 61A

PROJECT &amp; ENG. ORDER NO.

C 43 - 400 - 001 B

SHEET / OF /

DATE 5-20-76

TEST PLAN NO. C#3-002

MODEL NO ULHX-II

PART NO. 5VSK 90348-1

SERIAL NO.

OPERATORS Kille

Time	TEST POINT No.	TIN OF	PIN PSIA	Flow lb/hr	$\Delta P$ "H <sub>2</sub> O	Flow %
2210.	1	67.9	14.6	20	.34	22*
2220	2	68.2	14.6	30	.67	32.5
2230	3	68.3	14.6	40.	1.06	42.5
2240	4					unable To get required lb/hr.

REMARKS:

REMARKS: Flow rate FR 116-34  
\* CURVE EXTENDED

22499



SPACE &amp; LIFE SYSTEMS LABORATORY

### LOG OF TEST

TYPE OF TEST  
PERFORMANCE. Dry

TEST ENGINEER  
E. Moore

NAME OF RIG  
61 / 61 A

PROJECT & ENG. ORDER NO.  
C43-400-001B

SHEET 1 OF DATE 5-21-76

TEST PLAN NO. C43-002

MODEL NO. LLL 4x II

PART NO. SVSK 90348-1

**SERIAL NO.**

OPERATORS KUL/E

TEST Point	Time	← H <sub>2</sub> O LOOP →										← AIR SIDE →						DEW POINT	LOW DO	HIGH DO		
		Circ	Flow	Flow	Temp	Temp	ΔT	Pin	ΔP	ΔP	Flow	Pin	Temp	ΔP	Temp	Temp	Flow				D.P.in	D.P.out
No.			CPS	#/hr	°F	°F	°F	PSIG	"H <sub>2</sub> O	"H <sub>2</sub> O	#/hr	"H <sub>2</sub> O	"H <sub>2</sub> O	"H <sub>2</sub> O	°F	°F	°F	°/min	°F	°F	°C/in	°F
3	1820	Prim	976	1009.7	43.2	62.8	19.5	25.0	62.0	.61	36	.94	.40	.55	104.1	46.1	58.2	22.76	26.5	22.5	0	61.4
3	1825	Prim	975	1008.6	43.2	62.7	19.8	25.0	62.0	.60	36	.93	.40	.54	104.5	46.0	58.4	22.77	26.0	22.0	0	61.6
3	1830	Prim	975	1008.6	43.1	62.7	19.6	25.0	61.9	.60	36	.94	.40	.55	104.5	46.0	58.4	22.74	25.5	22.5	0	61.5
3	1835	Prim	975	1008.6	43.1	62.8	19.6	25.0	62.0	.60	36	.94	.39	.54	104.5	46.1	58.3	22.75	26.0	23.0	0	61.6
3	1840	Prim	977	1010.7	43.1	62.9	19.7	25.0	62.0	.60	36	.94	.40	.54	104.7	46.2	58.4	22.76	26.0	23.0	0	61.5
3	1845	Prim	975	1008.6	43.3	62.9	19.5	25.0	62.0	.60	36	.93	.40	.54	104.5	46.3	58.0	22.74	26.0	23.0	0	61.1
2		Prim	990	1024.3	49.2	60.6	11.5	25.0	62.5	.58	36	1.03	.42	.60	84.8	50.9	33.7	23.52	25.0	22.0	0	36.0
2		Prim	990	1024.3	49.1	60.6	11.6	25.0	62.5	.58	36	1.03	.42	.60	85.0	50.8	34.1	23.51	24.5	22.0	0	35.9
2		Prim	993	1027.4	49.0	60.7	11.6	25.0	62.5	.58	36	1.02	.42	.59	85.2	50.8	34.2	23.52	24.5	22.0	0	36.1
2		Prim	990	1024.3	49.1	60.8	11.7	25.0	62.5	.58	36	1.03	.42	.60	85.3	50.9	34.3	23.50	24.5	22.5	0	36.1
2		Prim	992	1026.4	49.1	60.9	11.8	25.0	62.5	.58	36	1.03	.42	.60	85.4	50.9	34.4	23.54	24.5	22.5	0	36.2
2		Prim	990	1024.3	49.1	61.0	11.8	25.0	62.5	.58	36	1.03	.42	.60	85.5	51.0	34.5	23.53	24.5	22.5	0	36.3
1		Prim	449	462.5	42.2	50.5	8.0	25.1	17.0	.83	36	.10	0	.10	79.7	43.7	35.9	7.67	7.0	1.0	0	37.1
1		Prim	448	461.4	42.1	50.6	8.2	25.1	17.0	.83	36	.10	0	.10	79.5	43.8	35.6	7.64	7.0	1.0	0	37.0
1		Prim	450	463.5	41.8	50.3	8.1	25.1	17.0	.83	36	.10	0	.10	79.2	43.6	35.5	7.68	7.0	1.0	0	36.9
1		Prim	448	461.4	41.9	50.5	8.3	25.1	17.0	.83	36	.10	0	.10	79.6	43.6	36.0	7.69	7.0	1.0	0	37.6
1		Prim	447	460.4	41.8	50.4	8.6	25.1	17.0	.83	36	.10	0	.10	79.9	43.6	36.3	7.64	7.0	1.0	0	38.1
1		Prim	445	458.3	41.9	50.6	8.5	25.1	17.0	.83	36	.10	0	.10	80.0	43.6	36.3	7.69	7.0	1.0	0	38.0

## REMARKS:

REMARKS:

\* K Factor for 460 = 1.03  
K Factor for 1025 = 1.0347  
K Factor for 1009 = 1.0345

14140

~~REPRODUCIBILITY OF THE~~  
ORIGINAL PAGE IS POOR

HSP-175 1A 1/66 <b>Hamilton Standard</b> DIVISION OF UNITED AIRCRAFT CORPORATION WINDSOR LOCKS, CONNECTICUT 06096  <b>SPACE &amp; LIFE SYSTEMS LABORATORY</b> <b>LOG OF TEST</b>										<b>TYPE OF TEST</b> Performance Dry & Wet <b>TEST ENGINEER</b> E. Moore <b>NAME OF RIG</b> 61-61A <b>PROJECT &amp; ENG. ORDER NO.</b> C-43-400-601B										<b>SHEET 1 OF</b> <b>DATE 5/24/76</b> <b>TEST PLAN NO</b> C-43-002 <b>MODEL NO.</b> LLL Hx-TI <b>PART NO.</b> SVSK 90378-1 <b>SERIAL NO</b> <b>OPERATORS</b> SANDBERG									
TEST POINT	TIME	CIRCL	FLOW	FLOW	TIN	TOOT	ΔT	PIN	ΔP	ΔP	FLOW	PIN	POUT	ΔP	TIN	TOOT	ΔT	FLOW	DPIN	DPOUT	CONDEN SATE OUT	H <sub>2</sub> O/H <sub>2</sub> O IN/OUT							
NO			CPS	#/hr	OF	OF	OF	PSIG	"H <sub>2</sub> O	"H <sub>2</sub> O	#/hr	"H <sub>2</sub> O	"H <sub>2</sub> O	"H <sub>2</sub> O	OF	OF	OF	#/min	OF	OF	cc/min	OF							
3	10:40	SEC.	976	1009.6	43.5	63.4	19.9	25.0	56.5	.62	36	.92	.38	.53	103.4	46.3	56.9	22.76	21.0	17.0	0	60.3							
3	10:45	SEC	976	1009.6	43.4	63.6	20.2	25.0	56.5	.62	36	.91	.38	.54	103.9	46.4	57.3	22.75	21.0	17.0	0	60.7							
3	10:50	SEC	976	1009.6	43.5	63.6	20.1	25.5	56.5	.62	36	.91	.38	.54	104.0	46.5	57.2	22.76	21.0	17.0	0	60.7							
3	10:55	SEC	976	1009.6	43.6	63.7	20.1	25.5	56.5	.62	36	.91	.38	.55	104.2	46.5	57.3	22.76	21.0	17.5	0	61.0							
3	11:00	SEC	976	1009.6	43.6	63.8	20.2	25.5	56.5	.62	36	.91	.38	.55	104.1	46.6	57.2	22.76	21.0	17.5	0	61.1							
3	11:05	SEC	976	1009.6	43.4	63.9	20.3	25.5	56.5	.62	36	.91	.38	.55	104.3	46.6	57.5	22.76	21.0	18.0	0	61.5							
WET																													
3	12:50	SEC	977	1010.7	43.3	66.5	23.2	25.0	55.5	2.45	36	1.04	.40	.65	103.5	49.3	54.0	22.76	58.0	47.0	BURRITT STAT- 1000	60.7							
1	12:55	SEC	977	1010.7	43.5	66.5	23.0	25.0	55.0	2.45	36	1.04	.40	.65	103.7	49.4	54.2	22.76	58.0	47.0	860	60.8							
	13:00	SEC	976	1009.6	43.5	66.5	23.0	25.0	55.5	2.50	36	1.04	.40	.65	103.7	49.4	53.9	22.76	58.0	47.0	745	60.5							
	13:05	SEC	976	1009.6	43.6	66.0	22.5	25.0	55.5	2.45	36	1.04	.40	.65	103.6	49.4	54.1	22.76	57.5	47.0	600	60.6							
4	13:10	SEC	977	1010.7	43.4	66.2	22.8	25.0	55.5	2.45	36	1.04	.40	.66	103.6	49.4	54.1	22.76	57.8	47.0	480	60.6							
3	13:15	SEC	977	1010.7	43.4	66.2	22.8	25.0	55.5	2.45	36	1.04	.40	.66	103.7	49.3	54.1	22.76	57.8	47.0	350	60.7							
																				TOTAL	650CC	25/MIN.							
																				CONDENSATE FLOW =	26 CC/MIN.								
REMARKS:																													
K-Fact. @ 4.60 1.03 =																													
@ 1.025 1.0347 =																													
@ 1.009 1.0345 =																													

14141

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

**U  
A**

SPACE &amp; LIFE SYSTEMS LABORATORY

## LOG OF TEST

TYPE OF TEST  
PERFORMANCE WETTEST ENGINEER  
E. MOORENAME OF RIG  
G1 + G1APROJECT & ENG. ORDER NO.  
C43-400-001 B

SHEET OF DATE 5/24/74

TEST PLAN NO C43-002

MODEL NO. LLL HX-II

PART NO SVSK 90348-1

SERIAL NO.

OPERATORS SANDBERG

C.B. 29.55 "HGABS

TEST POINT	TIME	CIRC	COOLANT H <sub>2</sub> O			SLURPER			AIR CIRCUIT			COND. OUT			H <sub>2</sub> O IN/AIR IN							
			FLOW CPS	TEMP °F	TOUT °F	ΔT °F	PIN PSIG	ΔP "H <sub>2</sub> O	FLOW F/H <sub>2</sub> O	PIN "H <sub>2</sub> O	POUT "H <sub>2</sub> O	ΔP "H <sub>2</sub> O	TIN °F	TOUT °F		ΔT °F	FLOW F/H <sub>2</sub> O	DPIN °F	DPOUT °F			
3	13:40	PRIM	976	1009.6	43.8	65.7	22.1	25.0	66.0	2.42	36	1.04	.40	.66	103.8	49.2	54.3	22.76	57.5	48.0	START 1000	60.3
3	13:45	PRIM	976	1009.6	43.6	65.7	22.1	25.0	66.0	2.42	36	1.04	.40	.66	103.9	49.2	54.4	22.76	57.5	48.0	867	60.3
3	13:50	PRIM	976	1009.6	43.6	65.6	22.1	25.0	66.0	2.42	36	1.04	.40	.65	103.8	49.2	54.4	22.77	57.5	48.0	740	60.3
3	13:55	PRIM	976	1009.6	43.5	65.6	22.1	25.0	66.0	2.42	36	1.04	.40	.65	103.8	49.2	54.6	22.76	57.7	48.0	618	60.3
3	14:00	PRIM	976	1009.6	43.6	65.5	22.0	25.0	66.0	2.42	36	1.04	.40	.65	103.6	49.2	54.4	22.76	57.7	48.0	490	60.1
3	14:05	PRIM	976	1009.6	43.6	65.6	22.1	24.75	66.0	2.42	36	1.04	.40	.65	103.9	49.1	54.6	22.76	57.7	48.0	360	60.3
																					TOTAL	640 CC/25 MIN
																						25.6 CC/MIN
																						START
2	14:50	PRIM	991	1025.3	49.1	62.0	13.0	25.5	67.5	2.3	36	1.11	.43	.68	85.6	52.1	33.5	23.51	55.5	51.0	1000	36.6
2	14:55	PRIM	991	1025.3	49.0	61.9	12.9	25.5	67.5	2.3	36	1.11	.43	.68	85.5	52.0	33.2	23.51	55.5	50.5	940	36.5
2	15:00	PRIM	991	1025.3	49.1	61.8	12.8	25.5	67.5	2.3	36	1.11	.43	.68	85.1	52.0	33.0	23.51	55.5	50.5	886	36.2
2	15:05	PRIM	992	1026.4	49.1	61.8	12.9	25.5	68.0	2.3	36	1.11	.43	.67	85.3	52.0	33.1	23.53	55.5	50.5	835	36.4
2	15:10	PRIM	991	1025.3	48.9	61.8	12.8	25.5	67.5	2.3	36	1.10	.43	.68	85.3	52.1	33.1	23.52	55.5	50.5	780	36.3
2	15:15	PRIM	991	1025.3	48.9	61.8	12.8	25.5	67.5	2.3	36	1.10	.43	.68	85.2	52.1	33.0	23.52	55.5	50.5	725	36.2
																					TOTAL	275 CC/25 MIN
																						11 CC/MIN

## REMARKS

K FACTOR C460 = 1.03  
C1025 = 1.0347  
C1009 = 1.0345

14142

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

**U  
A**

## SPACE &amp; LIFE SYSTEMS LABORATORY

## LOG OF TEST

## TYPE OF TEST

PERFORMANCE

## TEST ENGINEER

E. MOORE

## NAME OF RIG

G1 + G1A

## PROJECT &amp; ENG. ORDER NO.

C43-400-001 B

## SHEET

OF

DATE 5-24-76

TEST PLAN NO. C43-002

MODEL NO. LLL HX II

PART NO. SVSK 90348-1

## SERIAL NO

OPERATORS Craghton

TEST POINT	TIME	← COOLANT →		H <sub>2</sub> O				→ SLURPER ←				← AIR CIRCUIT →						→ COND ←		IN AIR IN ΔT OF			
		CIRC	FLOW	FLOW	TIN	TOUT	ΔT	PIN	ΔP	ΔP	FLOW	PIN	POUT	ΔP	TIN	TOUT	ΔT	FLOW	DP IN		DP OUT	OUT	
			CPS	#/HR	°F	°F	°F	PSIG	"H <sub>2</sub> O	"H <sub>2</sub> O	#/HR	"H <sub>2</sub> O	"H <sub>2</sub> O	"H <sub>2</sub> O	"H <sub>2</sub> O	°F	°F	°F	#/MIN	°F	°F	Start	OF
1		Prim	446	459.4	42.1	53.3	11.3	25.5	21.5	2.48	36	13	0	13	79.8	44.8	35.0	7.68	53.5	42.8	1000	38.0	
1		Prim	446	459.4	42.1	53.2	11.2	25.5	21.5	2.48	36	13	0	13	79.8	44.8	35.0	7.67	53.6	42.8	967	37.8	
1		Prim	447	460.4	42.1	53.2	11.3	25.5	21.5	2.48	36	13	0	13	80.0	44.8	35.0	7.68	53.6	42.8	930	38.0	
1		Prim	447	460.4	42.1	53.1	11.2	25.5	21.5	2.48	36	13	0	13	80.0	44.8	35.1	7.69	53.5	42.8	894	38.0	
1		Prim	446	459.4	42.1	53.2	11.2	25.5	21.5	2.48	36	13	0	13	80.1	44.8	35.1	7.69	53.5	42.8	860	38.0	
1		Prim	446	459.4	42.1	53.1	11.2	25.5	21.5	2.48	36	13	0	13	80.0	44.9	35.0	7.69	53.6	42.8	824	38.0	
																					Total	176 cc/25 min	
																						7.04 cc/min	
																</							

## REMARKS:

K Factor @ 460° = 1.03  
@ 1025° = 1.0347

C.B. @ 70° 29.53 "Hg  
Psi 14.5005

14143

HMF-175.1A 1/66 <b>Hamilton Standard</b> DIVISION OF UNITED AIRCRAFT CORPORATION WINDSOR LOCKS, CONNECTICUT 06096  SPACE & LIFE SYSTEMS LABORATORY LOG OF TEST										TYPE OF TEST TEST ENGINEER NAME OF RIG PROJECT & ENG. ORDER NO.										SHEET OF DATE TEST PLAN NO. MODEL NO. PART NO. SERIAL NO. OPERATORS									
HMF-175.1A 1/66 <b>Hamilton Standard</b> DIVISION OF UNITED AIRCRAFT CORPORATION WINDSOR LOCKS, CONNECTICUT 06096  SPACE & LIFE SYSTEMS LABORATORY LOG OF TEST										TYPE OF TEST TEST ENGINEER NAME OF RIG PROJECT & ENG. ORDER NO.										SHEET OF DATE TEST PLAN NO. MODEL NO. PART NO. SERIAL NO. OPERATORS									
Test Point	Time	Circ	Flow	Flow	Tin	Tout	AT	Pin	AP	AP	Flow	Tin	Pin	Pout	AP	Circuit	Tin	Tout	AT	Flow	Ppin	Ppout	H <sub>2</sub> O						
			CPS	#/hr	°F	°F	°F	Rig	1/20	1/20	#/hr	°F	1/20	1/20	1/20	°F	°F	°F	°F	#/min	°F	°F	°F						
2		Prim	991	1025.4	48.3	60.9	12.2	25.3	68	.43	30	60	1.02	.43	.6	85.7	50.2	35.3	23.54	26.5	24.8	37.1							
2		Prim	991	1025.4	48.2	60.4	11.8	25.5	68.2	.43	30	60	1.02	.43	.6	85.4	50.2	35.2	23.51	26.6	24.8	37.0							
2		Prim	991	1025.4	48.3	60.5	11.8	25.4	68.5	.43	30	60	1.02	.43	.6	85.7	50.3	35.2	23.51	26.7	24.8	37.1							
2		Prim	991	1025.4	48.4	60.5	11.7	25.4	68.5	.43	30	60	1.02	.43	.6	85.7	50.4	35.2	23.51	26.8	24.9	36.9							
2		Prim	991	1025.4	48.4	60.6	11.8	25.4	68.5	.43	30	60	1.02	.43	.6	85.6	50.4	35.2	23.51	27.0	25.2	36.9							
2		Prim	991	1025.4	48.4	60.6	11.7	25.4	68.2	.43	30	60	1.02	.43	.6	85.7	50.5	35.2	23.51	27.2	25.3	36.9							
SHARP COND.										5/25/74																			
2	1	PRIM	992		49.9	61.1	11.3	25.5	68.5	.04	20	61.0	1.04	.46	.6	84.7	51.5	33.0	23.52	25.0	23.0	34.9							
1	2	PRIM	992		49.9	61.2	11.4	25.5	68.5	.36	30	61.0	1.01	.43	.6	84.9	51.6	33.1	23.51	25.5	23.5	35.0							
	3	PRIM	992		49.9	61.3	11.4	25.5	68.5	.73	40	61.0	.98	.40	.6	85.1	51.6	33.2	23.51	26.0	24.0	35.2							
	*4	PRIM	991		49.6	61.3	11.5	25.5	68.5	1.5	50	58.0	.90	.33	.58	85.3	51.5	33.6	23.51	27.0	25.0	35.4							
	*1	PRIM	991		49.8	61.4	11.5	25.5	68.5	.08	20	58.0	1.05	.46	.6	85.5	51.6	33.8	23.51	26.0	24.0	35.6							
	*2		991		49.7	61.4	11.5	25.5	68.5	.45	30	58.0	1.0	.43	.58	85.6	51.6	33.8	23.51	26.0	24.0	35.7							
V	*3		991		49.7	61.4	11.6	25.5	68.5	.93	40	57.0	.96	.39	.58	85.6	51.5	33.9	23.51	26.5	24.5	35.9							
2	*4	PRIM	991		49.6	61.3	11.7	25.5	68.5	1.5	50	56.0	.92	.34	.58	85.7	51.4	34.1	23.51	27.2	25.5	36.1							
REMARKS: * BYPASSED COLLECTION BOTTLES TO SECURE HIGHER FLOW ON F/R.																													

14145



**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

U  
D AIRC  
A

SPACE &amp; LIFE SYSTEMS LABORATORY

### LOG OF TEST

TYPE OF TEST

COOLANT RIG TARE

**TEST ENGINEER**

E. MOORE

NAME OF RIG

$$G_1 + G_1 A$$

**PROJECT & ENG. ORDER NO.**

CH3-400-001B

SHEET OF

DATE 5/25/74

TEST PLAN NO. ENG INSTR & TABLE III

MODEL NO.

PART NO.

SERIAL NO.

OPERATORS SANDBERG

LOOP	TEST POINT	TIN °F	PIN PSIG	FLOW CPS	FLOW T <sup>2</sup> /HR	K FACTOR	ΔP "H <sub>2</sub> O
SEC.	4	44.5	25.5	1160	1201.4	1.0357	23.0
SEC.	3	45.4	25.5	965	1001.3	1.0345	16.2
SEC.	2	45.2	25.0	775	800.4	1.0328	11.2
SEC.	1	44.7	25.0	582	600.3	1.0315	6.5
PRIM	4	45.6	25.0	1160	1201.4	1.0357	37.0
PRIM	3	45.3	24.5	968	1001.3	1.0345	26.5
PRIM	2	44.9	25.0	775	800.4	1.0328	17.5
PRIM	1	45.0	24.5	582	600.3	1.0315	10.5

REMARKS:

INLET & OUTLET CONNECTED BY  $\frac{5}{8}$  O.D. TUBE,  $3\frac{1}{2}$ " LG. ( $\frac{17}{32}$  I.D.)

14146

REPRODUCIBILITY OF THE  
ORIGINAL PAGE IS POOR

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

U  
A

SPACE &amp; LIFE SYSTEMS LABORATORY

## LOG OF TEST

## TYPE OF TEST

WEIGHT

## TEST ENGINEER

E. K. MOORE

## NAME OF RIG

12

## PROJECT &amp; ENG ORDER NO.

C43-100-001B

SHEET 1 OF

DATE 5-27-76

TEST PLAN NO. C43-002

MODEL NO. LLL HX II

PART NO. SVSK 90348-1

SERIAL NO.

OPERATORS SLAHTOSKY

	FIRST DRY CYCLE	SECOND DRY CYCLE
START TIME	0930	12:30
END TIME	1130	14:30
TEMP @ START	105.0°	130.0
TEMP @ END	145.0°	135.0
VACUUM @ START	.6 MM	.5
VACUUM @ END	.3 MM	.3
TIME @ WEIGHING	11:30	14:45
WEIGHT	19.26	19.26

REMARKS:

14116

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

**U  
A**

SPACE &amp; LIFE SYSTEMS LABORATORY

## LOG OF TEST

## TYPE OF TEST

PROOF - LKG

## TEST ENGINEER

E.K. MOORE

## NAME OF RIG

64

## PROJECT &amp; ENG. ORDER NO.

C43-400-001 B

SHEET 1 OF

DATE 5-28-76

TEST PLAN NO C43-503 A

MODEL NO. LLL HX II

PART NO. SVSK 96348-1

SERIAL NO.

OPERATORS SLAHTOSKY

						PRIMARY LOOP		SECONDARY LOOP		AIR LOOP	
BAROMETRIC PRESS, "HG						30.03		30.03		30.03	
AMB. TEMP. OF						70.0		70.0		70.0	
INITIAL PRESS PSIG						90.0		90.0		1.8	
ITEM TEMP. OF						72.0		72.0		72.0	
PRESS IN 10. MIN. PSIG						90.0		90.0		1.79	
" 15. " "						90.0		90.0		1.77	
" 20. " "						90.0		90.0		1.74	
" 25. " "						90.0		90.0		1.72	
" 30. " "						90.0		90.0		1.70	
TEMP 10. MIN OF						72.0		72.0		72.0	
" 15 " "						72.0		72.0		72.0	
" 20 " "						72.0		72.0		72.0	
" 25 " "						72.0		72.0		72.0	
" 30 " "						72.0		72.0		72.0	
PRESS @ 89.5 IN 90.0 MINUTES PRIMARY LOOP											

REMARKS

22548

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

U  
D AIRC  
A

**SPACE & LIFE SYSTEMS LABORATORY**

### LOG OF TEST

### TYPE OF TEST

LK E.

**TEST ENGINEER**

E. K. MOORE

NAME OF RIG

64

PROJECT &amp; ENG ORDER NO.

C43-400-001B

SHEET / OF

DATE 6-7-76

TEST PLAN NO. 10 C

MODEL NO. 444 HX

PART NO. SVSK 90348

**SERIAL NO.**

OPERATORS SLAH TOSK ✓

PIN	TIME
PSIG	MINUTES
1.8	0
1.5	60.

REMARKS.

14120

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

U  
A

SPACE &amp; LIFE SYSTEMS LABORATORY

## LOG OF TEST

## TYPE OF TEST

PROOF + LKG.

## TEST ENGINEER

E. K. MOORE

## NAME OF RIG

64

## PROJECT &amp; ENG. ORDER NO

C43-400-001B

SHEET 1 OF

DATE 6-10-76

TEST PLAN NO. 1.0C dC43-002-1744

MODEL NO. LLL HX II

PART NO. SYSK90348-1

SERIAL NO.

OPERATORS SLAHTESKY

## PRIMARY LOOP

BAROMETRIC PRESS. IN HG

29.72

AMB. TEMP. OF

72.0

INITIAL PRESS PSIG

90.0

INLET TEMP OF

73.0

PRESS IN 10 MIN PSIG

90.0

15 "

90.0

20 "

89.9

25 "

89.9

30 "

89.85

50 "

89.8

60 "

89.8

70 "

89.75

110 "

89.6

120 "

89.55

212 "

89.00

6-11-76

INVERTED BEAKER LKG. PRIMARY LOOP TO SECONDARY LOOP = 8.0 CCHR.

REMARKS:

14131

HSP 175 1A 1/66 <b>Hamilton Standard</b> DIVISION OF UNITED AIRCRAFT CORPORATION WINDSOR LOCKS, CONNECTICUT 06096  <b>SPACE &amp; LIFE SYSTEMS LABORATORY</b> <b>LOG OF TEST</b>												TYPE OF TEST <b>PERFORMANCE</b> TEST ENGINEER <b>E. K. Moore</b> NAME OF RIG <b>61, 61A</b> PROJECT & ENG. ORDER NO. <b>C43-400-001B</b>				SHEET <b>1 A</b> OF <b>DATE 6/21/76</b> TEST PLAN NO. <b>LAC. C43-002 PH. 5 TABLE V</b> MODEL NO. <b>LLH HX II</b> PART NO. <b>SUSK 90348-1</b> SERIAL NO. OPERATORS <b>Sandberg Oeignton</b>									
TEST POINT	TIME	H <sub>2</sub> O CIRC.	H <sub>2</sub> O FLOW	H <sub>2</sub> O FLOW FACTOR	K	H <sub>2</sub> O IN	H <sub>2</sub> O OUT	H <sub>2</sub> O LST	H <sub>2</sub> O PIN	H <sub>2</sub> O DP	AIR FLOW	AIR FLOW	TIN	TOUT	AT	PIN	POUT	AP	AIR IN	AIR OUT	DP IN	DP OUT			
NO			CPS	%/HR		OF	OF	OF	PSIG.	"H <sub>2</sub> O	#/MIN.	#/HR.	°F	°F	°F	"H <sub>2</sub> O	"H <sub>2</sub> O	"H <sub>2</sub> O	ΔT OF	°F	°F				
1	1430	PRIM	443	459.8	1.038	42.0	53.8	12.4	26.0	21.2	7.62	457.2	79.9	45.0	34.6	+1.3	-0.08	.22	38.1	55.5	43.0				
2	1435		443	459.8		42.1	53.8	12.3	26.0	21.2	7.62	457.2	79.8	45.1	34.7	+1.3	-0.08	.22	38.0	55.5	43.0				
3	1440		443	459.8		41.9	53.8	12.3	26.0	21.2	7.62	457.2	79.9	45.1	34.7	+1.3	-0.08	.22	38.2	55.5	43.0				
4	1445		442	459.7		42.1	53.8	12.3	26.0	21.2	7.63	457.2	79.8	45.0	34.7	+1.3	-0.08	.22	38.2	55.5	43.0				
5	1450		442	459.7		42.2	53.8	12.3	26.0	21.2	7.63	457.2	79.8	45.1	34.7	+1.3	-0.08	.22	38.1	55.5	43.0				
6	1455		443	459.8	1.038	42.2	53.8	12.3	26.0	21.2	7.63	457.2	79.8	45.1	34.7	+1.3	-0.08	.22	38.1	55.5	43.0				
7A	1510		443	459.8	1.038	42.3	53.9	12.5	26.0	21.2	7.69	461.4	79.8	45.1	34.7	-0.15	-0.42	.22	38.2	55.5	43.0				
8A	1520		443	459.8	1.038	42.4	53.9	12.1	26.0	21.2	7.69	461.4	79.7	45.1	34.5	-0.15	-0.42	.22	38.1	55.5	43.0				
9A	1530		443	459.8	1.038	42.5	53.8	12.4	26.0	21.2	7.69	461.4	79.8	45.1	34.5	-0.14	-0.40	.22	38.1	55.5	43.0				
10A	1540		443	459.8	1.038	42.4	53.8	12.5	26.0	21.2	7.69	461.4	79.8	45.2	34.5	-0.15	-0.41	.23	38.1	55.5	43.0				
11B			443	459.8	1.038	41.9	53.4	12.2	26.0	21.2	7.69	461.4	79.5	44.9	34.4	-0.4	-0.66	.24	38.1	55.5	43.0				
12B			443	459.8	1.038	42.1	53.4	12.2	26.0	21.2	7.69	461.4	79.3	44.9	34.3	-0.4	-0.66	.24	37.8	56.0	43.0				
13B			443	459.8	1.038	41.9	53.3	12.1	26.0	21.2	7.69	461.4	79.4	44.9	34.4	-0.4	-0.66	.24	38.1	56.0	43.0				

REMARKS.  
 \* UNSTABLE

13662

REPRODUCIBILITY OF THE  
ORIGINAL PAGE IS POOR

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

U  
A

## SPACE &amp; LIFE SYSTEMS LABORATORY

## LOG OF TEST

## TYPE OF TEST

PERFORMANCE

## TEST ENGINEER

E. K. MOORE.

## NAME OF RIG

61,61A

## PROJECT &amp; ENG. ORDER NO.

C43-400-001 B

SHEET 18 OF

DATE 6-21-76

TEST PLAN NO. C43-002 PHAS TABLE V

MODEL NO. LLL HX II

PART NO. SVSK 90348-1

SERIAL NO.

OPERATORS SANDBERG Creighton

TEST POINT R/O	SLURP IN	SLURP OUT	SLURP ΔP	STEAM H <sub>2</sub> O * FLOW	COND. CURRENT	CONIX CC	CONIX CC/5 MIN	CONIX CC/30 MIN	CONIX CC/HR	SLURPER SEPARATOR ORIFICE	SLURP H <sub>2</sub> O	SLURP ΔP H <sub>2</sub> O	CR.
#	"H <sub>2</sub> O	"H <sub>2</sub> O	"H <sub>2</sub> O	SCALE #/HR	CC	CC/5 MIN	CC/30 MIN	CC/HR	"H <sub>2</sub> O	"ΔP H <sub>2</sub> O	"H <sub>2</sub> O	"H <sub>2</sub> O	"H <sub>2</sub> O
1	-1.08	-2.6	2.48	8 1.4	500 462	38				-4.6	138	29.92	
1	-1.08	-2.6	2.48	8 1.4	462 426	36				-4.6	138	29.92	
1	-1.08	-2.55	2.47	8 1.4	426 387	39				-4.6	138	29.92	
1	-1.08	-2.55	2.48	8 1.4	387 350	37				-4.6	138	29.92	
1	-1.08	-2.55	2.48	8 1.4	350 311	39				-4.6	138	29.92	
1	-1.06	-2.6	2.48	8 1.4	311 272	39	228	100		-4.6	138	29.92	
1A	-1.42	-2.1	1.73	8 1.4	500 400	100				-3.6	125	29.92	
1A	-1.42	-2.1	1.74	8 1.4	400 315	85				-3.6	125	29.92	
1A	-1.40	-2.1	1.73	8 1.4	500 401	99				-3.6	125	29.92	
1A	-1.41	-2.1	1.75	8 1.4	500 413	87	371	123		-3.6	125	29.92	
1B	-1.66	-1.7	1.06	8 1.4	500 408	102				-2.6	125	29.89	
1B	-1.66	-1.7	1.06	8 1.4	500 400	100				-2.6	125	29.89	
1B	-1.66	-1.7	1.08	8 1.4	500 398	102	304	134		-2.6	113	29.89	

REMARKS:

\* F/R 102-22 (1/8-20 SA)

13663



**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

**U  
A**

SPACE &amp; LIFE SYSTEMS LABORATORY

## LOG OF TEST

## TYPE OF TEST

Perf.

## TEST ENGINEER

EK Moose

## NAME OF RIG

61,61A

## PROJECT &amp; ENG. ORDER NO

C43-400-001B

SHEET 1A OF DATE 6-21-76

TEST PLAN NO C43-002 JP 4.5 Table II

MODEL NO. 22L HX II

PART NO. SYSK 90348-1

SERIAL NO.


OPERATORS Creighton

Test Point	Time	H <sub>2</sub> O Circ	H <sub>2</sub> O Flow	H <sub>2</sub> O Flow	K Factor	H <sub>2</sub> O In	H <sub>2</sub> O Out	H <sub>2</sub> O AT	H <sub>2</sub> O Pin	H <sub>2</sub> O Pout		Air Flow	Air Flow	T <sub>in</sub> Air	T <sub>out</sub> Air	AT Air	P <sub>in</sub> Air	P <sub>out</sub> Air	ΔP Air	Air / H <sub>2</sub> O In	DP In	DP Out
No			CPM	#/hr		%	%	%	PSIG	"H <sub>2</sub> O		#/min	#/hr	%	%	%	"H <sub>2</sub> O	"H <sub>2</sub> O	"H <sub>2</sub> O	Δ°F	°F	°F
* 2		Prim	986	1024.94	1.0395	48.9	62.7	14.1	25.2	65		23.54	1412.4	85.3	52.7	32.4	1.80	.68	1.18	36.4	56/60	51.8
2			988	1027.03	1.0395	49.0	62.6	14.0	25.2	67		23.54	1412.4	85.3	52.7	32.3	1.80	.68	1.18	36.4	56/60	51.9
2			986	1024.94	1.0395	49.1	62.7	13.7	25.2	67		23.54	1412.4	85.1	52.6	32.4	1.80	.68	1.18	36.2	56/60	51.8
* 2A		Prim	984	1022.81	1.0395	49.0	62.8	13.9	25.2	66.5		23.54	1412.4	85.4	52.9	32.3	1.38	.22	1.17	36.2	56/60	51.8
2A			985	1023.91	1.0395	49.1	62.8	13.9	25.2	67.0		23.54	1412.4	85.4	53.0	32.3	1.38	.22	1.17	36.2	56/60	51.8
2A			987	1025.99	1.0395	49.1	62.8	13.8	25.2	67.0		23.54	1412.4	85.4	52.9	32.4	1.38	.22	1.17	36.2	56/60	51.8
* 2B		Prim	988	1027.03	1.0395	49.1	62.8	13.9	25.0	67.5		23.54	1412.4	85.6	53.0	32.4	1.0	7.8	1.17	36.4	56/60	51.8
2B			986	1024.94	1.0395	49.0	62.7	13.9	25.0	67.5		23.54	1412.4	85.6	52.8	32.6	1.02	7.8	1.17	36.7	56/60	51.8
2B			988	1027.03	1.0395	49.1	62.7	13.7	25.0	68.0		23.54	1412.4	85.7	52.8	32.6	1.02	7.8	1.17	36.4	56/60	51.7

## REMARKS:

\* Air Pin Unstable, Inlet Dew Point also

13664

HSF-175.1A 1/66		<div style="text-align: center;">  </div>		TYPE OF TEST <i>Perf.</i>				SHEET <i>1B</i> OF <i>13</i> DATE <i>6-21-76</i>					
Hamilton Standard DIVISION OF UNITED AIRCRAFT CORPORATION WINDSOR LOCKS, CONNECTICUT 06096				TEST ENGINEER <i>EK Moore</i>				TEST PLAN NO. <i>C43-002 D4.5 Table I</i>					
SPACE & LIFE SYSTEMS LABORATORY				NAME OF RIG <i>61, 61A</i>				MODEL NO. <i>LLH HX-II</i>					
				PROJECT & ENG. ORDER NO. <i>CH3-400-001B</i>				PART NO. <i>SVSK 9034B-1</i>					
LOG OF TEST								SERIAL NO.					
								OPERATORS <i>Creighton</i>					

Test Point No	SWRP IN	SWRP OUT	SWRP AP	Steam Flow Scale	H <sub>2</sub> O #/Hr	Cond. Barlett	Cond. CC	Cond. CC	Cond. CC	Cond. #/Hr	SWRP Separator	CB						
2	1.58	-1.9	2.49	10.3	2.3	50°/24	182				-4.5, 43	29.89						
2	1.58	-1.9	2.5	10.3	2.3	50°/24	180			1	-4.5, 43	29.89						
2	1.58	-1.9	2.5	10.3	2.3	50°/24	182	544	23986		-4.5, 43	29.89						
2A	1.22	-1.8	1.94								-3.4							
2A	1.22	-1.8	2.06	10.3	2.3	50°/24	180				-3.5, 285	29.89						
2A	1.22	-1.8	2.09	10.3	2.3	50°/24	175			1	-3.5, 285	29.89						
2A	1.22	-1.85	2.07	10.3	2.3	50°/24	180	535	23589		-3.5, 280	29.89						
2B	-1.8	1.8	1.63	10.3	2.3	50°/24	176				-2.7, 140	28.89						
2B	-1.8	1.75	1.62	10.3	2.3	50°/24	174			1	-2.7, 140	28.89						
2B	-1.8	1.8	1.63	10.3	2.3	50°/24	174	524	2310		-2.7, 140	28.89						
3												29.97						

REMARKS: \* FR 102-22 (1/2 - 20 SA)

13665

HSP-175 1A 1/66

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

U  
A

SPACE &amp; LIFE SYSTEMS LABORATORY

## LOG OF TEST

TYPE OF TEST

PERFORMANCE.

TEST ENGINEER

E. K. Moore

NAME OF RIG

C1+C1A

PROJECT &amp; ENG. ORDER NO

CH3-400-601B

SHEET 1 OF DATE G-22-79

TEST PLAN NO C43-002 PH-S TABLE V

MODEL NO. LLL HX II

PART NO. SVSK 90348-1

SERIAL NO.

OPERATORS SANDBERG

TEST POINT	TIME	H <sub>2</sub> O CIRC	H <sub>2</sub> O FLOW	H <sub>2</sub> O FLOW	K FACTOR	H <sub>2</sub> O IN	H <sub>2</sub> O OUT	H <sub>2</sub> O ΔT	H <sub>2</sub> O PIN	H <sub>2</sub> O ΔP	AIR FLOW	AIR FLOW	TIN AIR	TOVT AIR	ΔT AIR	PIN AIR	POVT AIR	ΔP AIR	AIR IN	ΔT IN	DR IN	DR OUT
NO			CPS	#/HR		°F	°F	°F	PSIG	"H <sub>2</sub> O	#/MIN.	#/HR	°F	°F	°F	"H <sub>2</sub> O	"H <sub>2</sub> O	"H <sub>2</sub> O	ΔT °F	°F	°F	°F
3	1000	PRIM	969	1007.2	1.0395	42.4	65.1	23.2	24.5	65.5	22.77	1366.2	104.0	48.0	55.8	1.61	1.56	1.12	62.4	58.0	47.0	
3	1010	PRIM	968	1006.2	1.0395	42.2	65.1	23.2	24.5	66.0	22.76	1365.6	104.2	48.0	55.9	1.65	1.56	1.11	62.3	58.0	46.8	
3	1020	PRIM	966	1004.1	1.0395	42.2	65.0	23.2	24.5	65.5	22.78	1366.8	104.3	47.9	56.0	1.65	1.56	1.11	62.4	58.0	46.8	
3A	1050	PRIM	969	1007.2	1.0395	42.3	65.0	23.2	24.5	66.0	22.81	1368.6	104.3	47.9	56.2	1.31	1.20	1.11	62.4	58	46.8	
3A	1100	PRIM	970	1008.3	1.0395	42.3	65.0	23.3	24.5	66.0	22.81	1368.8	104.5	47.9	56.1	1.35	1.24	1.11	62.6	58.5	47.0	
3A	1110	PRIM	969	1007.2	1.0395	42.4	65.0	23.3	24.5	66.0	22.82		104.5	47.9	56.3	1.35	1.24	1.11	62.5	58.5	47.0	
3B	1220	PRIM	968	1006.2	1.0395	42.0	65.1	23.4	24.5	66.0	22.81	1368.8	104.3	47.8	56.6	1.08	1.02	1.13	62.7	55/59	46.8	
3B	1230	PRIM	970	1008.3	1.0395	41.9	64.8	23.3	24.5	66.0	22.80	1368	104.1	47.7	56.1	1.08	1.03	1.12	62.2	55/59	46.8	
3B	1240	PRIM	970	1008.3	1.0395	42.1	64.8	23.0	24.5	66.0	22.86	1371	104.0	47.8	56.2	1.08	1.05	1.13	62.1	57/59	46.8	

REMARKS:

\* UNSTABLE

13666

REPRODUCIBILITY OF THE  
ORIGINAL PAGE IS POOR

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

## SPACE &amp; LIFE SYSTEMS LABORATORY

### LOG OF TEST

TYPE OF TEST  
PERFORMANCE

**TEST ENGINEER**

E. K. MOORE

NAME OF RIG

61 + 61A

PROJECT & ENG ORDER NO.

C43-400-001B

SHEET 1A OF DATE 6-22-75

TEST PLAN NO C43-002 TP4.5 TABLE V

MODEL NO. LLL HX II

PART NO. SVS/K90348-1

**SERIAL NO.**

OPERATORS *SANDBERG*

[illegible]

REMARKS:

REMARKS:  
F/R 102-22 (1/8-20 SA)

13667

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

**U  
A**

SPACE &amp; LIFE SYSTEMS LABORATORY

## LOG OF TEST

## TYPE OF TEST

PERFORMANCE

TEST ENGINEER

E. K. MOORE

NAME OF RIG

G1 + G1 A

PROJECT &amp; ENG ORDER NO.

C43-400-001B

SHEET 1 OF

DATE 6-22-76

TEST PLAN NO C43-002 P4.5 TABLE V

MODEL NO. ALL HX II

PART NO SVSK90348-1

SERIAL NO.

OPERATORS SANDBERG

TEST POINT	TIME	H <sub>2</sub> O CIR.	H <sub>2</sub> O FLOW CPS	H <sub>2</sub> O FLOW #/HR	K FACTOR	H <sub>2</sub> O T <sub>IN</sub> °F	H <sub>2</sub> O T <sub>OUT</sub> °F	H <sub>2</sub> O ΔT °F	H <sub>2</sub> O P <sub>IN</sub> PSIG	H <sub>2</sub> O ΔP "H <sub>2</sub> O	AIR FLOW #/MIN	AIR FLOW #/HR	T <sub>IN</sub> AIR °F	T <sub>OUT</sub> AIR °F	AT AIR °F	P <sub>IN</sub> AIR "H <sub>2</sub> O	P <sub>OUT</sub> AIR "H <sub>2</sub> O	ΔP AIR "H <sub>2</sub> O	AIR IN H <sub>2</sub> O ΔT °F	DP IN °F	DP OUT °F
4	1410	SEC	969	1007.2	1.0395	41.9	65.5	23.6	24.5	61.5	22.73	1363.8	104.1	48.2	55.6	1.62	.53	1.11	62.7	57/59	46
4	1420	SEC	970	1008.3	1	41.9	65.5	23.6	24.5	61.5	22.73	1363.8	104.1	48.3	55.6	1.62	.53	1.11	62.6	57/59	46
4	1430	SEC	970	1008.3	1	42.1	65.6	23.5	24.5	61.5	22.76	1365.6	104.1	48.4	55.6	1.63	.53	1.11	62.7	57/60	46
4A	1500	SEC	972	1010.3	1.0395	42.1	65.6	23.5	24.5	61.5	22.76	1365.6	104.3	48.4	55.7	1.32	.22	1.12	62.7	58/60	46.5
4A	1510	SEC	970	1008.3	1	42.1	65.6	23.5	24.5	61.5	22.76	1365.6	104.3	48.5	55.7	1.32	.24	1.12	62.6	57/60	46.5
4A	1520	SEC	970	1008.3	1	42.0	65.6	23.6	24.5	61.5	22.76	1365.6	104.2	48.5	55.7	1.32	.22	1.12	62.6	57/60	46.5
4B	1640	SEC	972	1010.3	1.0395	43.5	66.9	23.4	24.5	61.0	22.77	1366.2	104.5	49.6	54.8	1.15	-.07	1.21	61.8	57/62	47.8
4B	1650	SEC	970	1008.3	1	43.3	66.6	23.3	24.5	61.0	22.77	1366.2	104.6	49.5	55.0	1.15	-.07	1.21	61.9	57/62	47.5
4B	1700	SEC	970	1008.3	1	43.4	66.5	23.1	24.5	60.5	22.77	1366.2	104.6	49.5	55.0	1.15	-.07	1.21	61.8	57/62	47.8
4C	1750	SEC	971	1009.35	1.0395	43.5	66.7	23.2	24.5	61.0	22.77	1366.2	104.6	49.7	55.0	1.67	.50	1.17	61.8	57/62	47.8
4C	1800	SEC	970	1008.3	1	43.6	66.5	22.9	24.5	61.0	22.77	1366.2	104.8	49.7	54.8	1.68	.53	1.17	61.8	57/62	47.8
4C	1810	SEC	970	1008.3	1	43.5	66.7	23.2	24.5	61.0	22.77	1366.2	104.7	49.7	54.8	1.68	.53	1.17	61.8	57/62	47.8

REMARKS:

13669

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

**U  
A**

**SPACE & LIFE SYSTEMS LABORATORY**  
**LOG OF TEST**

## TYPE OF TEST

PERFORMANCE

## TEST ENGINEER

E. K. MOORE

## NAME OF RIG

C1+C1A

## PROJECT &amp; ENG ORDER NO.

C43-400-000R

SHEET 1A OF

DATE 6-22-76

TEST PLAN NO. C43-002 TP 4.5 TABLE V

MODEL NO. LLL 17X II

PART NO. SVSK 90348-1

SERIAL NO.

OPERATORS SANDBERG

TEST POINT	SLURP IN	SLURP OUT	SLURP AP	STEAM H <sub>2</sub> O FLOW	COND REPORT	COND CC/S MIN	COND CC/MIN	COND #/HR	SLURP SEPARATOR OR FILE	P IN H <sub>2</sub> O	P AP H <sub>2</sub> O	CB						
	"H <sub>2</sub> O	"H <sub>2</sub> O	"H <sub>2</sub> O	F/R SCALE	#/HR.													
4	+53	-2.1	2.59	16.3	4.75	500/341	159	31.8	4.2	-4.4	.41	29.98						
4	.53	-2.1	2.60	16.3	4.75	500/340	160	32.0	4.23	-4.4	.41	29.98						
4	.53	-2.1	2.60	16.3	4.75	500/340	160	32.0	4.23	-4.4	.41	29.98						
L CONTINUED COLLECTION TO 250 CC IN 7 MIN. 45 SEC = 32.25 CC/MIN = 4.26 #/HR.																		
4A	.22	-2.0	2.17	16.3	4.75	500/340	160	32	4.23	-3.5	.27	29.98						
4A	.23	-2.0	2.19	16.0	4.60	500/340	160	32	4.23	-3.5	.27	29.98						
4A	.23	-2.0	2.19	16.2	4.70	500/341	159	31.8	4.2	-3.5	.27	29.98						
L CONTINUED COLLECTION TO 250 CC IN 8 MIN 0 SEC = 31.25 CC/MIN = 4.13 #/HR																		
4B	-0.7	-1.85	1.78	16.1	4.65	500/336	165	33	4.365	-2.7	.14	29.98						
4B	-0.7	-1.85	1.74	16.1	4.65	500/336	164	32.8	4.339	-2.7	.14	29.98						
4B	-0.7	-1.85	1.73	16.2	4.70	500/336	165	33	4.365	-2.7	.14	29.98						
L CONTINUED COLLECTION TO 250 CC = 7.857 min = 31.82 cc/min = 4.21 #/HR																		
4C	.50	-2.0	2.51	16.2	4.70	500/340	165	33	4.365	-4.5	.41	29.98						
4C	.53	-2.0	2.54	16.2	4.70	500/340	162	32.4	4.286	-4.5	.41	29.98						
4C	.53	-2.0	2.56	16.2	4.70	500/340	165	33	4.365	-4.5	.41	29.98						
L CONTINUED COLLECTION TO 250 CC = 7.8 min = 32.05 cc/min = 4.2395 #/HR																		

## REMARKS:

F/R 10222 (1/8 -20.9A)

10200 CC collected @ 3140° 6/22/76  
Condensate ahead of HX.  
572 cc @ 1830 Hrs 6/22/76

13668

13671

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

SPACE &amp; LIFE SYSTEMS LABORATORY

### LOG OF TEST

### TYPE OF TEST

## Performance

**TEST ENGINEER**

FK Moore

## NAME OF RIG

61. 61A

## PROJECT &amp; ENG ORDER NO.

C 43-403-000 B

SHEET 1A OF DATE 6-22-76

TEST PLAN NO. CH3-002 P 4.5 Table V

MODEL NO. 262 HX II

PART NO. *SVSK 90348-1*

SERIAL NO

OPERATORS *Creighton*

Test Point	Slur P Pin	Slur P Port	Slur P AP	Steam H <sub>2</sub> O Flow	Cond Blaslett	Cond	Cond	Cond	Cond	Slur per Separator Gravimetric Pin H <sub>2</sub> O AP 1/20	CB					
No	1/20	1/20	1/20	FR Scale #/Hr	cc	cc/5 min	cc/min	#/Hr			H <sub>2</sub> /AB					
4D	.28	-2.5	2.84	16.1 4.65	500/23	163	32.6	4.31		-4.6 .36	29.98					
4D	.35	-2.6	2.88	16.1 4.65	500/23	157	31.4	4.15		-4.6 .36	29.98					
4D	.35	-2.6	2.86	16.1 4.65	500/24	155	31.0	4.10		-4.6 .36	29.98					
Continued collection to 250 cc = 7.783 min = 32.43 cc min = 4.29 #/Hr																

## REMARKS.

REMARKS. F/R 102-22 (18-20 GA)

Started H<sub>2</sub>O Flow Steam 2130Hrs <sup>4/22</sup> Shut down ~~at~~ 0010 6/23 collected 580 cc ahead of HX (up stream)

13672

REPRODUCIBILITY OF THE  
ORIGINAL PAGE IS POOR.



**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

SPACE &amp; LIFE SYSTEMS LABORATORY

### LOG OF TEST

### TYPE OF TEST

AIR PRESSURE DROP TEST DAY

**TEST ENGINEER**

E. MOURE

NAME OF RIG

61

PROJECT &amp; ENG. ORDER NO.

C43-4100-001B

SHEET OF

OF

DATE 7-7-76

TEST PLAN NO C43-002 TABLE II

MODEL NO. L66 HX II

PART NO. SVSK 90348-1

**SERIAL NO.**

OPERATORS SANDBERG

TEST POINT	PIN	POUT	$\Delta P$	TIN	TOUT	DPIN	DPOUT	Flow D/MIN	Flow GPM	CR HGAB
1	.37	.12	.23	79.5	78.7	11.5	12.5	11.66	699.6	29.77
2	.70	.23	.44	80.8	80.7	19.5	19.5	16.65	999.0	29.77
3	1.31	.54	.78	104.7	103.4	34.5	37.5	22.75	1365	29.79
4	1.63	.67	.96	88.7	80.3	35.0	35.0	26.66	1599.6	29.79

REMARKS

13571

**Hamilton Standard** DIVISION OF UNITED AIRCRAFT CORPORATION  
WINDSOR LOCKS, CONNECTICUT 06096

SPACE &amp; LIFE SYSTEMS LABORATORY

### LOG OF TEST

TYPE OF TEST WITH  
AIR PRESSURE DROP TEST. SLURPER.

TEST ENGINEER  
E. MOORE.

NAME OF RIG

PROJECT &amp; ENG ORDER NO.

C43-400-001B

SHEET OF DATE 7-8-76

TEST PLAN NO C 43-002 TABLE II

MODEL NO. LLL Hx II

PART NO 3VSK 90348-1

SERIAL NO.

OPERATORS SANDBERG

[illegible]

REMARKS:

13570

APPENDIX D  
ABBREVIATIONS AND SYMBOLS

ABBREVIATIONS AND SYMBOLS

ave	average
BTU	British Thermal Units
°C	degrees Centigrade
cc	cubic centimeters
cm	centimeters
d.a.	dry air
DA	double amplitude
db	decibels
°F	degrees Fahrenheit
g	gravity
g	grams
h	enthalpy
hg	mercury
hr	hour
Hz	Hertz
in	inches
k	kilo
K	degrees Kelvin
lat	latent
lbs	pounds
lr	leak rate
m	meter
max	maximum
min	minute
min.	minimum
mm	millimeters
N	Neinfons
N <sub>2</sub>	nitrogen
Pa	Pascals
psi	pounds per square inch
q	Btu/lb
Q	Btu/hr
R	universal gas constant
sec	second
sen	sensible
T	temperature
TDP	dew point temperature
t	time
V	volume
W	weight
∠	angle
#	lb
%	percent
Δ	delta
ε	effectiveness
"	inches